

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

JACK 3530 RECEIVED WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

MAY 20 1974

State Well No.

STATE ENGINEER

SALEM, OREGON

State Permit No.

35S/2W-14

G-8679

(1) OWNER:

Name Harold HOLDER
Address 15582 ANTIQUA RD.
CENTRAL POINT, ORE.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(10) LOCATION OF WELL:

County JACKSON Driller's well number
1/4 N.W. 1/4 Section 14 T. 35S R. 2W. W.M.

Bearing and distance from section or subdivision corner

APPRO. 2,400' E. AND 35'S. FROM
N.W. CORNER

(11) WATER LEVEL: Completed well.

Depth at which water was first found 31 ft.

Static level 13 ft. below land surface. Date 5-15-74

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 305 ft. Depth of completed well 305 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
SOIL, BROWN	0	2	
CLAY, BROWN	2	11	
CLAYSTONE, BLUE	11	32	
SANDSTONE, BLUE	32	128	
BASALT, BLUE (HARD)	128	160	
CLAYSTONE, BLUE	160	223	
BASALT, BLUE (HARD)	223	269	
CLAYSTONE, BLUE	269	276	
BASALT, BLUE (HARD)	276	305	13

(5) CASING INSTALLED:

6" Diam. from 0 ft. to 21 ft. Gage .250
" Diam. from " ft. to " ft. Gage
" Diam. from " ft. to " ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from " ft. to " ft.
Diam. Slot size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " "

" " "

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used PRESSURE Cement Grout

Well sealed from land surface to 9580 ft.

Diameter of well bore to bottom of seal 958 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 4 sacks

Number of sacks of bentonite used in well seal sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

Work started 5-14 19 74 Completed 5-15 19 74

Date well drilling machine moved off of well 5-15 19 74

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Ronald Martinez Date 5-15, 1974

(Drilling Machine Operator)

Drilling Machine Operator's License No. 622

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name MARTINSON WELL DRILLING

(Person, firm or corporation)

(Type or print)

Address 81 BALL RD. EAGLE POINT, ORE.

[Signed] J.W. Matison

(Water Well Contractor)

Contractor's License No. 406 Date 5-15, 19 74