

WATER WELL REPORT
STATE OF OREGON

RECEIVED

OCT 2 1 1982

State Well No.

355/2W-21

WATER RESOURCES DEPT.
SALEM, OREGON

State Permit No.

(1) OWNER:

Name John Stout
Address 12896 Perry Road
City Central Point State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
e ☐ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from +2 ft. to 18 ft. Gauge .250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

4" Diam. from 0 ft. to 240 ft. Gauge .250

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used skill saw
Size of perforations 1/8 in. by 7 in.
160 perforations from 160 ft. to 240 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
d: gal./min. with ft. drawdown after hrs.
" " " " " "
Air test 100+ gal./min. with drill stem at 238 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Portland Cement
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 6 sacks
How was cement grout placed? pressure grout tremie pipe
Was pump installed? no Type HP Depth ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number 82-61
1/4 1/4 Section 21 T. 35 R. 2W W.M.
Tax Lot # 1100 Lot Blk Subdivision
Address at well location: 12896 Perry Road

(11) WATER LEVEL: Completed well.

Depth at which water was first found 218 ft.
Static level 85 ft. below land surface. Date 9-18-82
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6 inch

Depth drilled 240 ft. Depth of completed well 240 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
soil--brown	0	1	
clay--yellow	1	10	
claystone--dark grey	10	100	
--light grey	100	142	
--brown	142	154	
--grey	154	162	
sandstone--grey	162	218	
--light grey	218	219	
claystone--grey	219	236	
sandstone--fractured	236	238	
claystone--light grey	238	240	

Work started 9-17 1982 Completed 9-18 1982
Date well drilling machine moved off of well 9-18 1982

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] John Studebaker Date 10-15, 1982
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1008

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Studebaker Well Drilling
(Person, firm or corporation) (Type or print)

Address 4876 Highway 66 Ashland, Oregon 97520

[Signed] John Studebaker
(Water Well Contractor)

Contractor's License No. 679 Date 10-15-82, 1982

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690