

WATER WELL REPORT
STATE OF OREGON

RECEIVED

JUL 22 1981

State Well No.

35/200-25

WATER RESOURCES DEPT
SALEM, OREGON

State Permit No.

(1) OWNER:

Name Dick Collman
Address 5538 Table Rock Rd
City Central Point State Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
Cable ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal: ☐ Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from 1 1/2 ft. to 38 1/2 ft. Gauge 1.250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

4" Diam. from 155 ft. to 18 ft. Gauge 1.250

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used skill saw
Size of perforations 1/8 in. by 4 in.
318 perforations from 7.9 ft. to 15.4 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

nd: gal./min. with ft. drawdown after hrs.
" " " " "

Air test 100 gal./min. with drill stem at 154 ft. 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 53 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement

Well sealed from land surface to 38 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 13 sacks

How was cement grout placed? pressure grout

Was pump installed? Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number 81-29
1/4 1/4 Section 25 T. 33 R. 2W W.M.
Tax Lot # 300 Lot Blk Subdivision

Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 81 ft.

Static level 27 ft. below land surface. Date 6-24-81

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 155 ft. Depth of completed well 155 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
clay sticky	0	3	
clay stone HARD	3	28	
Laminated Blue AND GREY claystone with WEATHERED BROWN sandstone layers	28	51	
Shale Rock	51	90	
clay stone	90	118	19
Metomorphic Rock with high Quartz content	118	144	
clay stone	144	145	
	145	155	19
* Primary water			
* RETRINGS FORMATION			

Work started 6-24 19 81 Completed 6-25 19 81

Date well drilling machine moved off of well 6-25 19 81

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] John Studelaker Date 6-30-81
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1008

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name STUDEBAKER WELL DRILL
(Person, firm or corporation)

Address 4876 Hwy 66 Ashland

[Signed] John Studelaker
(Water Well Contractor)

Contractor's License No. 679 Date 6-25-81

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690