

WATER RESOURCES DEPARTMENT.
SALEM, OREGON 97310
within 30 days from the date
of well completion.
Corrected by WRD staff

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No.

State Permit No.

(1) OWNER:

Name Roy L. Carver

Address 622 McDonough Rd.

Gold Hill, Ore.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6 " Diam. from 0 ft. to 20 ft. Gage See #12
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations in. by in.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Is a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " " " "

" " " " " "

Filter test 140 gal./min. with 125 ft. drawdown after 1 1/2 hrs.

Artesian flow _____ g.p.m.

Temperature of water _____ Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 19 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 6 sacks

How was cement grout placed? pressure grouted

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number _____

SW 1/4 NW 1/4 Section 129 T. 35S R. 2W W.M.

Bearing and distance from section or subdivision corner

Tax lot--3605 Permit--378-80W

(11) WATER LEVEL: Completed well.

Depth at which water was first found 91 ft.

Static level 20 ft. below land surface. Date 8/22/80

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6 in.

Depth drilled 145 ft. Depth of completed well 145 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil--brown	0	4	
Sandstone--brown	4	10	
Sandstone--gray	10	130	
Sandstone--pink	130	140	
Sandstone--gray	140	145	20
SDR26 (class 160) PSI PVC NSF type 1120			
ASTM 2241			
RECEIVED			
SEP 05 1980			
WATER RESOURCES DEPT			
SALEM, OREGON			

Work started 8/22 19 80 Completed 8/22 19 80

Date well drilling machine moved off of well 8/22 19 80

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] John J. Owens Date 8/25, 19 80
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1242

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Virgle Gribble Well Drilling
(Person, firm or corporation) (Type or print)

Address 8380 Ramsey Rd., Gold Hill, Or.

[Signed] Virgle Gribble
(Water Well Contractor)

Contractor's License No. 705 Date 8/25, 19 80