

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. _____

State Permit No. _____

WATER RESOURCES DEPT.

(1) OWNER:

Name Holmes, Thomas H.
Address 3285 Hollywood Ave
Medford, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
"6" Diam. from 1 ft. to 19 ft. Gage 350
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used _____

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " "

325
Bailer test 16 gal./min. with 11 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 19 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 52 sacks
Number of sacks of bentonite used in well seal _____ sacks
Brand name of bentonite _____
Number of pounds of bentonite per 100 gallons
of water _____ lbs./100 gals.

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Jackson Driller's well number 1 of 2
1/4 1/4 Section 34 T. 35 R. 2N W.M.

Bearing and distance from section or subdivision corner 550 ft.
225' E of the S.W. property
CORNER TABLE-ROCK + TRESHAM

(11) WATER LEVEL: Completed well.

Depth at which water was first found 52 ft.

Static level 21 ft. below land surface. Date 26 May 76

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 140 ft. Depth of completed well 140 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
SOIL	0	1	
CLAY	1	9	
SANDSTONE	9	52	
SANDSTONE BROKEN	52	55	21
CLAYSTONE	55	76	
CLAYSTONE BROKEN	76	78	21
CLAYSTONE	78	117	
SANDSTONE BROKEN	117	119	21
SANDSTONE	119	131	
SANDSTONE BROKEN	131	132	21
SANDSTONE	132	140	

Work started 25 May 1976 Completed 26 May 1976

Date well drilling machine moved off of well 26 May 1976

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] SEERULACK Date 26 May 76
(Drilling Machine Operator)

Drilling Machine Operator's License No. 819

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Crater Well Drilling Inc.
(Person, firm or corporation) (Type or print)

Address 1923 Delta Waters Rd. Medford

[Signed] Charles D. Chittwood
(Water Well Contractor)

Contractor's License No. 545 Date 5-27, 1976