

JACK
53245

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)
Instructions for completing this report are on back of form

JUN 14 1999

WATER RESOURCES DEPT.
SALEM, OREGON

WELL ID # **L28589**

(START CARD) # **118224**

(1) OWNER: Well Number: **2**
Name **Greg Hollister**
Address **575 Judge road**
City **Central Point** State **OR** Zip **97502**

(2) TYPE OF WORK:
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well **140** ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount	
Diameter	From	To	Material	From	To	sacks or pounds	
10	0	18	bentonite	0	18	7 sacks	
6	18	140					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other **poured dry**
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:							
Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6	+2	18	.250	☒	☐	☐	☐
Liner: 4	3	140	160	☐	☒	☒	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:							
☒ Perforations		Method skillsaw					
☐ Screens		Type		Material			
From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
80	140	1/4x6	100			☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour			
☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian			
Yield gal/min	Drawdown	Drill stem at	Time
20	140	140	1 hr.

Temperature of Water **58** Depth Artesian Flow found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County **Jackson** Latitude Longitude
Township **35S** N or S. Range **2W** E or W. of WM.
Section **22** NW 1/4 NW 1/4
Tax lot **1300** Lot Block Subdivision
Street Address of Well (or nearest address) **Perry road**

(10) STATIC WATER LEVEL:
9 ft. below land surface. Date **5/16/99**
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found **89**

From	To	Estimated Flow Rate	SWL
89	92	20	9

(12) WELL LOG: Ground elevation _____

Material	From	To	SWL
top soil	0	1	
tan clay	1	8	
grey sandstone	8	89	
brown sandstone	89	92	9
green sandstone	92	140	

ASHLAND DRILLING, INC.
ALL AMERICAN PUMP CO.
600 South Pacific Hwy.
Talent, OR 97540
(541) 488-2827

Date started **5/16/99** Completed **5/16/99**

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed *William J. Kelly* WWC Number **1657**
Date **6/11/99**
Ashland Drilling Inc.

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed *William J. Kelly* WWC Number **1478**
Date **6/11/99**
Ashland Drilling Inc.