

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form

JACK 53846

WELL ID # L L40767

(START CARD) # 131293

(1) OWNER:

Well Number:

Name **Bill Rombach**
Address **101 South Riverside**
City **Medford** State **OR** Zip **97501**

(2) TYPE OF WORK:

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well **200** ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount	
Diameter	From	To	Material	From	To	sacks or pounds	
10	0	47	bentonite	0	47	23 sacks	
6	47	200					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other **poured dry**

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	+1	47	.250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4	4	200	160	☐	☒	☒	☐
					☐	☐	☐	☐

Final location of shoe(s) **47'**

(7) PERFORATIONS/SCREENS:

☒ Perforations Method **skilsaw**
☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
120	180	1/4x6	100			☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
11	200	200	1 hr.

Temperature of Water **59** Depth Artesian Flow found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County **Jackson** Latitude Longitude
Township **38S** N or S. Range **2W** E or W. of W.M.
Section **24** NE 1/4 NE 1/4
Tax lot **1503** Lot Block Subdivision
Street Address of Well (or nearest address) **6434 Dark Hollow road**

(10) STATIC WATER LEVEL:

39 ft. below land surface. Date **5/19/2000**
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found **72**

From	To	Estimated Flow Rate	SWL
72	88	11	39

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
brown clay	0	3	
tan clay	3	9	
grey clay with gravel	9	28	
tan sandstone	28	41	
grey sandstone	41	64	
green sanstone	64	72	
grey sandstone with quartz	72	88	39
shale	88	97	
grey granite	97	104	
shale	104	143	
grey granite	143	194	
shale	194	200	

RECEIVED

ASHLAND DRILLING

600 S. Pacific Hwy.
Talent, OR 97540

(503) 488-2827 772-1800

JUN 19 2000

WATER RESOURCES DEPT.
SALEM, OREGON

Date started **5/19/2000**

Completed **5/19/2000**

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed

William Rombach
Ashland Drilling Inc.

WWC Number **1657**

Date **6/13/00**

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed

William Rombach
Ashland Drilling Inc.

WWC Number **1478**

Date **6/13/00**

ORIGINAL - WATER RESOURCES DEPARTMENT

FIRST COPY - CONSTRUCTOR

SECOND COPY - CUSTOMER