

JACK 55742

55742

152802

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

GRIBBLE WELL DRILLING INC.

(START CARD) # 45002

(1) OWNER: Well Number L-60800
Name Kathleen Niskanen
Address 2599 Pioneer Rd
City Medford State Or Zip 97501

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 200 ft.
Explosives used Yes No Type _____ Amount _____

| HOLE | | | SEAL | | | Amount sacks or pounds |
|----------|------|-----|----------|------|----|---------------------------|
| Diameter | From | To | Material | From | To | |
| 10" | 0 | 40 | bent | 0 | 40 | 700lbs |
| 6" | 40 | 200 | | | | |

How was seal placed: Method A B C D E
 Other poured dry
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

| Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|------------|------|-----|-------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|
| Casing: 6" | +1 | 39 | 250 | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| Liner: 4" | 0 | 200 | 160 | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |

Final location of shoe(s) 39'

(7) PERFORATIONS/SCREENS:

Perforations Method saw
 Screens Type _____ Material _____

| From | To | Slot size | Number | Diameter | Tele/pipe size | Casing | Liner |
|------|-----|-----------|--------|----------|----------------|--------------------------|-------------------------------------|
| 100 | 140 | 10 | 30 | 1/8 | | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| 160 | 180 | 10 | 30 | 1/8 | | <input type="checkbox"/> | <input checked="" type="checkbox"/> |

(8) WELL TESTS: Minimum testing time is 1 hour

Pump Bailer Air Flowing Artesian

| Yield gal/min | Drawdown | Drill stem at | Time |
|---------------|----------|---------------|-------|
| 10 | | 200 | 1 hr. |

Temperature of Water 56 Depth Artesian Flow Found 56
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Jackson Latitude N42'15.820 Longitude W122'48.313
Township 38S N or S. Range 1W E or W. WM.
Section 15DB SE 1/4 SE 1/4
Tax Lot 301 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 4880 S Pacific Hwy
Phoenix, Or. 97535

(10) STATIC WATER LEVEL:
19' ft. below land surface. Date 9/13/02
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 107

| From | To | Estimated Flow Rate | SWL |
|------|-----|---------------------|-----|
| 107 | 111 | 6 | 19 |
| 134 | 138 | 2 | 19 |
| 142 | 144 | 2 | 19 |

(12) WELL LOG:
Ground elevation _____

| Material | From | To | SWL |
|----------------|------|-----|-----|
| brown soil | 0 | 6 | |
| brown gravel | 6 | 32 | |
| gray claystone | 32 | 200 | 19 |

RECEIVED
NOV 03 2003
WATER RESOURCES DEPT.
SALEM, OREGON

RECEIVED
OCT 15 2002
WATER RESOURCES DEPT.
SALEM, OREGON

RECEIVED
DEC 15 2003
WATER RESOURCES DEPT.
SALEM, OREGON

Date started 9/13/02 Completed 9/13/02

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
Signed Liz Millhous WWC Number 005
Date 10-10-02