

DEC 12 2003

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT
SALEM, OREGON

WELL I.D. # L 67129
START CARD # 158678

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER
Name HOFFMAN INNOVATIVE LAND GROUP LLC
Address 1704 ASHLAND MINE RD
City ASHLAND State OR Zip 97520

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 198' 1/2 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	78 1/2	VENT CHIPS	68	73	3 SACKS
6"	78 1/2	242	" "	0	68	29 1/3 SACKS

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other POURED DRY
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

Casing:	Diameter	From	To	Gauge	Steel				Plastic	Welded	Threaded
					10"	8"	6"	4"			
	6"	1 1/2	78 1/2	250	☒	☐	☐	☐	☐	☒	☐
					☐	☐	☐	☐	☐	☐	☐
					☐	☐	☐	☐	☐	☐	☐
					☐	☐	☐	☐	☐	☐	☐
Liner:	4"	-10 1/2	212 1/2	160	☐	☒	☒	☐	☐	☐	☐
					☐	☐	☐	☐	☐	☐	☐

Drive Shoe used ☐ Inside ☒ Outside ☐ None
Final location of shoe(s) 78 1/2

(7) PERFORATIONS/SCREENS:							
☐ Perforations Method _____							
☒ Screens Type <u>SLOTTED</u> Material <u>PVC SDR21</u>							
From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
92	212 1/2	.032				☐	☒
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour			
☐ Pump ☐ Bailer ☒ Air ☐ Artesian	Yield gal/min	Drawdown	Drill stem at
	125+		242
	80		142
	105		162

Temperature of water 56° Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County TAJALSON Latitude _____ Longitude _____
Township 39S N or S Range 1E E or W. WM.
Section 6 NE 1/4 SW 1/4
Tax Lot 1600 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 2155 ASHLAND MINE RD

(10) STATIC WATER LEVEL:
74 ft. below land surface. Date 12-5-03
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found SEE BELOW

From	To	Estimated Flow Rate	SWL
134	138	9 2/3	74
156	158	60+	74
171	176	30	74
190	201	25	74

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
CLAY BROWN	0	15	
GRANITE BROWN WEATH.	15	36	
GRANITE GREY w/ WH.	36		
QUARTZ & BROWN CLASTS			
PUNKY TO 70 THEN FIRM			
(SLURRY LOOKS GREEN RATHER THAN GREY)			
GRANITE DECOMP. OR	134		
SHEARED GREY/BROWN		138	
DIORITE DECOMP./SHEARED	138		
DARK GREY		156	
GRANITE GREY & BROWN	156		
BROKEN DECOMP./SHEARED		164	
GRANITE GREY/WHITE	164		
DECOMP./SHEARED		190	
GRANITE BROWN/ORANGE/	190		
WHITE/GREY DECOMP.		242	
CAVING IN PLACES			

Date started 12-2-03 Completed 12-5-03

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed Frank K... WWC Number 796 Date 12-7-03

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed Frank K... WWC Number 796 Date 12-7-03

ORIGINAL - WATER RESOURCES DEPARTMENT

FIRST COPY - CONSTRUCTOR

SECOND COPY - CUSTOMER

* INITIAL INSTALLATION OF LINER LAYS AT 198-199 FEET. CLEARED HOLE TO 206 FT, LOWERED LINER TO 212+ FT BUT LINER IS OBSTRUCTED AT 198+ FT.