

STATE OF OREGON  
WATER SUPPLY WELL REPORT  
(as required by ORS 537.765)

JEFF  
50539

WELL I.D. # L 23700  
START CARD # 102298

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number \_\_\_\_\_  
Name Paden Prichard  
Address 27450 SW Campbell Lane  
City West Linn State OR Zip 97068

(2) TYPE OF WORK  
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:  
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger  
☐ Other \_\_\_\_\_

(4) PROPOSED USE:  
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation  
☐ Thermal ☐ Injection ☐ Livestock ☐ Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval ☐ Yes ☐ No Depth of Completed Well 70 ft.  
Explosives used ☐ Yes ☒ No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE SEAL  
Diameter From To Material From To Sacks or pounds  
10" 0 18 bentonite 0 18 15 cks  
6" 18 70 \_\_\_\_\_

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E  
☒ Other Poured  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:  
Diameter From To Gauge Steel Plastic Welded Threaded  
Casing: 6" 1 18 250 ☒ ☐ ☒ ☐  
Liner: 6" 18 70 250 ☒ ☐ ☒ ☐

Final location of shoe(s) \_\_\_\_\_  
(7) PERFORATIONS/SCREENS:  
☒ Perforations Method factory  
☐ Screens Type \_\_\_\_\_ Material \_\_\_\_\_  
From To Slot size Number Diameter Tele/pipe size Casing Liner  
50 70 1/8" 236 6" ☐ ☒

(8) WELL TESTS: Minimum testing time is 1 hour  
☒ Pump ☐ Bailor ☐ Air ☐ Flowing  
Yield gal/min Drawdown Drill stem at Time  
18 ZERO \_\_\_\_\_ 2 hr  
Temperature of water 52 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done? ☐ Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use? ☐ Too little  
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Jefferson Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 13S N or S Range 9E E or W. WM.  
Section 16AA NE 1/4 NE 1/4  
Tax Lot 1500 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 26313 SW Metke Lane

(10) STATIC WATER LEVEL:  
9 ft. below land surface. Date 5-15-99  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 3'

| From                               | To        | Estimated Flow Rate | SWL      |
|------------------------------------|-----------|---------------------|----------|
| <u>3</u>                           | <u>10</u> | <u>20+</u>          | <u>3</u> |
| <u>(Sealed off the above zone)</u> |           |                     |          |
| <u>60</u>                          | <u>70</u> | <u>20+</u>          | <u>9</u> |

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

| Material                   | From      | To        | SWL      |
|----------------------------|-----------|-----------|----------|
| <u>Clay Soil</u>           | <u>0</u>  | <u>3</u>  |          |
| <u>Brown clay sand</u>     | <u>3</u>  | <u>10</u> | <u>3</u> |
| <u>Brown clay + gravel</u> | <u>10</u> | <u>60</u> |          |
| <u>Black Sand, Med.</u>    | <u>60</u> | <u>70</u> | <u>9</u> |

**RECEIVED**  
MAY 20 1999  
WATER RESOURCES DEPT.  
SALEM, OREGON

Date started 5-13-99 Completed 5-14-99

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Mark Kibler WWC Number Trinec Date 5-16-99

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
Signed John Skiles WWC Number 1658 Date 5-17-99