

STATE OF OREGON
WATER SUPPLY WELL REPORT
 (as required by ORS 537.765)

WELL I.D. # L 34648
 START CARD # 131777

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 1
 Name PHIL & LAURIE MAHOLLAND
 Address 28041 S HULT ROAD
 City BEAVERCREEK State OR Zip 97004

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
 Special Construction approval ☐ Yes ☒ No Depth of Completed Well 134 ft.
 Explosives used ☐ Yes ☒ No Type - Amount -

HOLE			SEAL			Sacks or pounds	
Diameter	From	To	Material	From	To		
12	0	18	BENTONITE	0	18	13 SACKS	
8	18	134					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other POURED DOWN DRY
 Backfill placed from ft. to ft. Material
 Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8	+2	32	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	6	-14	134	188	☒	☐	☒	☐
					☐	☐	☐	☐

Final location of shoe(s) NO SHOE USED

(7) PERFORATIONS/SCREENS:
☒ Perforations Method MACHINE CUT
☐ Screens Type SLOT Material STEEL

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
54	74	1/8 x 6	248	6	-	☐	☒
94	114	1/8 x 6	248	6	-	☐	☒
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump	☐ Bailer	☒ Air	☐ Flowing
Yield gal/min	Drawdown	Drill stem at	Time
20	0	133	1 hr.

Temperature of water 54° Depth Artesian Flow Found
 Was a water analysis done? ☐ Yes By whom
 Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
 Depth of strata:

(9) LOCATION OF WELL by legal description:

County JEFFERSON Latitude Longitude
 Township 12 N or S Range 15 E or W. WM.
 Section 34 (0) SE 1/4 SW 1/4
 Tax Lot 409 Lot Block Subdivision
 Street Address of Well (or nearest address)
GRIZZLY MTN OFF RAMMS ROAD


(10) STATIC WATER LEVEL:
28 ft. below land surface. Date 7/18/01
 Artesian pressure - lb. per square inch. Date -

(11) WATER BEARING ZONES:
 Depth at which water was first found 90'

From	To	Estimated Flow Rate	SWL
80	110	25+GPM	28

(12) WELL LOG:
 Ground Elevation

Material	From	To	SWL
SOIL & ROCK	0	8	
TAN CONG.	8	30	
BROWN CONG.	30	50	
BROWN SS CONG.	50	65	
TAN SS CONG.	65	75	
PURPLE CONG.	75	80	
COARSE GRAVEL	80	90	28
BLACK BASALT	90	110	28
BLUE CLAYSTONE	110	115	
RED CLAYSTONE	115	120	
TAN CONG.	120	134	



Date started 7/17/01 Completed 7/18/01

(unbonded) Water Well Constructor Certification:
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed WWC Number
 Date

(bonded) Water Well Constructor Certification:
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed WWC Number 1556
 Date 7/24/01