

STATE OF OREGON
WATER SUPPLY WELL REPORT
 (as required by ORS 537.765)

WELL I.D. # L 34653
 START CARD # 131783

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 2/7
 Name STAFFORD RANCHES
 Address 1110 NE LAUGHLIN ROAD
 City PRINEVILLE State OR Zip 97754

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☐ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☒ Other TEST HOLE

(5) BORE HOLE CONSTRUCTION:
 Special Construction approval ☐ Yes ☒ No Depth of Completed Well 817 ft.
 Explosives used ☐ Yes ☒ No Type - Amount -

HOLE			SEAL			Sacks or pounds	
Diameter	From	To	Material	From	To		
12	0	18	BENTONITE	0	18	30	SACKS
8	18	817					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other POURED DOWN DRY
 Backfill placed from ft. to ft. Material
 Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8	+2	-35	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	6	-17	817	188	☒	☐	☒	☐
					☐	☐	☐	☐

Final location of shoe(s) NO SHOE USED

(7) PERFORATIONS/SCREENS:

☒ Perforations Method MACHINE CUT
☐ Screens Type SLOT Material STEEL

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
597	617	1/8x4	248	6	-	☐	☒
657	677	1/8x4	248	6	-	☐	☒
717	757	1/8x4	248	6	-	☐	☒
797	817	1/8x4	248	6	-	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump	☐ Bailer	☒ Air	☐ Flowing
Yield gal/min	Drawdown	Drill stemat	Artesian
200	-	816	Time
			1 hr.

Temperature of water 75° Depth Artesian Flow Found
 Was a water analysis done? ☐ Yes By whom
 Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
 Depth of strata:

(9) LOCATION OF WELL by legal description:

County JEFFERSON Latitude Longitude
 Township 13 N or ☒ Range 13 ☒ or W. WM.
 Section 17 NE 1/4 NW 1/4
 Tax Lot 100 Lot Block Subdivision
 Street Address of Well (or nearest address) OFF NORRIS RD-WEST OF HWY97

(10) STATIC WATER LEVEL:

370 ft. below land surface. Date 8-22-01
 Artesian pressure - lb. per square inch. Date -

(11) WATER BEARING ZONES:

Depth at which water was first found 710

From	To	Estimated Flow Rate	SWL
710	817	300 + GPM	370

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
SOIL & ROCK	0	8	
BROWN CLAYSTONE CONG	8	60	
RED CINDERS	60	90	
BASALT	90	170	
TAN SS CONG	170	240	
BASALT	240	275	
BROWN SS CONG	275	560	
TAN SS CONG	560	590	
PINK CLAYSTONE	590	650	
BROWN SS CONG	650	710	
COARSE TAN SS CONG	710	817	370

RECEIVED

SEP 21 2001

WATER RESOURCES DEPT.
 SALEM, OREGON

Date started 8-16-01 Completed 8-22-01

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1556

Signed Dan Smith Date 9/17/01