

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

JAN 06 1986 RECEIVED DEC 30 1985 JOSE 12162

SALEM, OREGON

PLEASE TYPE or PRINT IN INK

(for official use only)

(1) OWNER:

Name LORAINÉ Wilson
Address 1127 GARDEN TERRACE
City GRANTS PASS State ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐
Cable ☐ Bored ☐ Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 60 ft. Gauge 2.50
" Diam. from 60 ft. to 250 ft. Gauge

LINER INSTALLED:

Steel ☐ Plastic ☐
Threaded ☐ Welded ☐
" Diam. from 0 ft. to 0 ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No
Size of perforations in. by in.
perforations from 0 ft. to 0 ft.
perforations from 0 ft. to 0 ft.
perforations from 0 ft. to 0 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from 0 ft. to 0 ft.
Diam. Slot Size Set from 0 ft. to 0 ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Well: gal./min. with ft. drawdown after hrs.
Air test 18 gal./min. with drill stem at 60 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 52 Depth artesian flow encountered 0 ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒
Well seal—Material used Cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Amount of sealing material 9 sacks ☒ pounds ☐
How was cement grout placed? pumped

Was pump installed? NO Type HP Depth ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from 0 ft. to 0 ft.

(10) LOCATION OF WELL by legal description:

County JOSEPHINE SE 1/4 SW 20 of
Township 36S Range 5W WM.
(Township is North or South) (Range is East or West)
Tax Lot 3400 Lot Block Subdivision

MAILING ADDRESS OF WELL (or nearest address)

1127 GARDEN TERRACE

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 60 ft.
Static level 7 ft. below land surface. Date 12-24-85
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6 ft.
Depth drilled 80 ft. Depth of completed well 80 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	3	
BROWN CLAY SMALL TO MEDIUM GRAVEL	3	19	
DECOMPOSED GRANITE	19	54	
FRACTURED Tombstone	54	80	7
AQUIFER	60	80	18gpm

Date work started 12-23-85 / completed 12-23-85
Date well drilling machine moved off of well 12-23 19 85

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Michael L. Linn Date 12-23, 19 85

(bonded) Water Well Constructor Certification:

Bond 2394665 Issued by: WESTERN SURETY
(number) (Surety Company Name)
On behalf of PAGIN DRILLING
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Bob Quinn
(Water Well Constructor)
(Dated) 12-24-85

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866-690