

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED

JUL 20 1989

39S/5W/466
#9727

County Permit # 3425

(START CARD) #

(1) OWNER:

Name Smith Const.

Well Number: 390

Address P.O. Box 420

City Williams

State ORE Zip

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 140 ft.

Explosives used Yes ☐ No ☒ Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10	0	20	Cement	0	20	13
8	20	65	Cement	20	65	JACKS
6	65	50				Cement

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Casing:	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
	4 1/2	1	2 1/2	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) 87 1/2

(7) PERFORATIONS/SCREENS:

☐ Perforations

Method

☐ Screens

Type

Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump

☐ Bailer

☒ Air

☐ Flowing
Artesian

Yield gal/min	Drawdown	Drill stem at	Time
40	17	140	1 hr

Temperature of water 56° Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County JOSE Latitude Longitude

Township 39 N or S, Range 5 E or W, WM.

Section 4 NW 1/4 NW 1/4

Tax Lot 347 Lot Block Subdivision

Street Address of Well (or nearest address) 121 Bon Linda

Dr. Williams.

(10) STATIC WATER LEVEL:

21' ft. below land surface.

Date 7/17/89

Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 70'

From	To	Estimated Flow Rate	SWL
70	140	40	21

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Brown clay + Granit	0	5	
Gray Brown Clay	5	11	
Gray clay + GRAVEL	11	30	
Gray Brown Clay + Boulders	30	52	
Gray clay + Decomposed Granit	52	70	21
HARD Gray Granit	70	140	21

Date started 7/16/89 Completed 7/17/89

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number

Signed Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 260

Signed Charles F. White Date