

RECEIVED DOSE 1922

NOTICE TO WATER WELL CONTRACTOR AUG 19 1965

The original and first copy of this report are to be filed with the

STATE ENGINEER WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310 OREGON STATE OF OREGON (Please type or print)

Jose 1922

State Well No. 37/5w-36 C

State Permit No.

(1) OWNER:

Jack Bennett G-5095

Name Mrs E. E. Walker
Address 273 Rubble Rd Grants Pass, Oregon

(2) LOCATION OF WELL:

County Josephine Driller's well number
NW 1/4 NW 1/4 Section 36 T. 37S.R. 5W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well X Deepening Reconditioning Abandonment

(4) PROPOSED USE (check):

Domestic Industrial Municipal Rotary Driven Cable Jetted Dug

(5) TYPE OF WELL:

(6) CASING INSTALLED:

6" Diam. from 0 ft. to 120-6 ft. Gage 1/4 wall

(7) PERFORATIONS:

Perforated Yes X No
Type of perforator used Hoe & Mills Perforator
Size of perforations 9/16 in. by 3 in.

(8) SCREENS:

Well screen installed? Yes X No
Manufacturer's Name
Model No.
Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite
Depth of seal 18 ft. Was a packer used?
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? Yes X No
Was a drive shoe used? Yes X No
Was well gravel packed? Yes X No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? Yes X No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 12 ft 6 in. ft. below land surface Date Aug 14/65
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? Yes No X If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
Bailer test 44 gal./min. with 23 ft. drawdown after 1 1/2 hrs.
Artesian flow g.p.m. Date
Temperature of water 59 degrees Was a chemical analysis made? Yes X No

(12) WELL LOG:

Diameter of well below casing 6 in.
Depth drilled 121 ft. Depth of completed well 121 ft.
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

Table with 3 columns: MATERIAL, FROM, TO. Entries include: Tan. granitic soil (0-47), Granite sand & gravel (46-58), Brown granite (48-93), Tan clay and granite (93-113), Coarse gray granite (113-121).

Work started Aug 9 19 65 Completed Aug 14 19 65
Date well drilling machine moved off of well Aug 14 19 65

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME BROWNER'S WELL DRILLING
Address GRANTS PASS, OREGON
Drilling Machine Operator's License No. 346

[Signed] Homer S. Browner (Water Well Contractor)
Contractor's License No. 414 Date Aug 14, 19 65



Oregon Water Resources Department
 725 Summer Street NE, Suite A
 Salem Oregon 97301
 (503) 986-0900
 www.oregon.gov/owrd

Application for Well ID Number

RECEIVED

NOV 10 2020

OWRD

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Schmidt Family Vineyards LLC
 Mailing Address: 242 Missouri Flat Rd
 City, State, Zip: Grants Pass, OR 97527
 Mail Well ID to: SAME AS ABOVE In Care Of (C/O)
 Name & Address: Attn: Cal Schmidt
 City, State, Zip: _____

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 37 S (North / South) Range: 5 W (East / West) Section: 36 NE 1/4 of the NW 1/4
 Tax Lot (usually last 3-5 numbers of Tax Map #): 601 County Josephine
 GPS Coordinates: 42.3156, -123.2399
 Street Address of Well, City: 242 Missouri Flat Rd
 If the property had a different street address in the past: _____

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Report, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Nursery
 Date Well Constructed (or property built): 1965 Total Well Depth: 102' Casing Diameter: 6"
 Owner at time the well was constructed (if known): Mr. E. E. Wilkin Well Report # (if known): JOSE1922/58376
 Other Information: Has two reports one for drilling in 1965 and one for new liner in 2009

SUBMITTED BY (please print): Sarah Schwab
 PHONE: 503-508-6028 EMAIL &/or FAX: sschwab@oda.state.or.us

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
 Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

***OWRD STAFF NOTES: I believe this well is "well #2" on Certificate 37562, and well driller simply duplicated the well ID tag from other well (JOSE 57639) onto their well report. Replacing tag with this one. LKA**

<i>For Official Use Only by the Oregon Water Resources Department:</i>		
Received Date: <u>11-10-2020</u>	Well Report Number: <u>JOSE 1922 - ORIG</u> <u>JOSE 58376 - ALT</u>	Well Identification #: <u>L 140915</u>