

STATE OF OREGON
 WATER SUPPLY WELL REPORT
 (as required by ORS 537.765)

WELL I.D. # L 83669

START CARD # 187187

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number 187187
 Name Norman & Melody Schmidt
 Address 2249 Reeves Creek Rd
 City Selma State OR Zip 97538

(2) TYPE OF WORK New Well
 Deepening Alteration (repair/recondition) Abandonment Conversion

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable Auger Cable Mud
 Other _____

(4) PROPOSED USE
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: Yes No
 Depth of Completed Well 160' ft.
 Explosives used: Yes No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds 10 Sacks
Diameter	From	To	Material	From	To	
10"	0'	20'	Bentonite	0'	20'	
6"	20'	160'				

How was seal placed: Method A B C D E

Other Bentonite Dry Poured

Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1'	39'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 4"	0'	160'	sch 40	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used Inside Outside None

Final location of shoe(s) 39'

(7) PERFORATIONS/SCREENS
 Perforations Method Factory
 Screens Type Screen/Slot Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
140'	160'	1/16x3	360			<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
7 GPM		160'	1 Hr

Temperature of water 55 Depth Artesian Flow Found _____

Was a water analysis done? Yes By whom _____

Did any strata contain water not suitable for intended use? Yes No

Salty Muddy Odor Colored Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)
 County Josephine
 Tax Lot 800 Lot _____
 Township 38 S Range 8 W WM
 Section 25 NW 1/4 NW 1/4

Lat _____ " or _____ (degrees or decimal)
 Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) 2249 Reeves Crk Rd Selma, OR

(10) STATIC WATER LEVEL
26' ft. below land surface. Date 5/25/06
 _____ ft. below land surface. Date _____
 Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES
 Depth at which water was first found 68'

From	To	Estimated Flow Rate	SWL
68'	71'	2 GPM	26'
93'	95'	1 GPM	26'
105'	108'	2 GPM	26'
151'	155'	2 GPM	26'

(12) WELL LOG Ground Elevation _____

Material	From	To	SWL
Brown Clay	0'	33'	
Black Shale Broken	33'	68'	
Black Shale	68'	160'	26'

Date Started 5/25/06 Completed 5/25/06

(unbonded) Water Well Constructor Certification
 I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification
 I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1835 Date 5/25/06

Signed [Signature] Clausen Drilling LLC

