

STATE OF OREGON

WATER SUPPLY WELL REPORT

(as required by ORS 537.765 & OAR 690-205-0210)

09-18-2008

WELL LABEL # L 97200

START CARD # 1004964

(1) LAND OWNER Owner Well I.D. _____
First Name JOHN Last Name SNOOK
Company _____
Address 5453 HUGO RD
City MERLIN State OR Zip 97532

(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)
Depth of Completed Well 140.00 ft.

BORE HOLE			SEAL			sacks/ lbs
Dia	From	To	Material	From	To	
10	0	26	Bentonite Chips	0	26	12 S
6	26	140				

How was seal placed. Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Dry Poured
 Backfill placed from _____ ft. to _____ ft. Material _____
 Filter pack from _____ ft. to _____ ft. Material _____ Size _____
 Explosives used: ☐ Yes Type _____ Amount _____

(6) CASING/LINER		Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thro
		6	☒	1.5	98.5	.250			☒	
			☐						☐	
			☐						☐	
			☐						☐	
			☐						☐	
			☐						☐	

Shoe ☐ Inside ☒ Outside ☐ Other Location of shoe(s) 98.5
Temp casing ☐ Yes Dia From To

(7) PERFORATIONS/SCREENS		
Perforations	Method	
Screens	Type	Material

[illegible]

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump
 ☐ Bailer
 ☒ Air
 ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
20		98	1

Temperature 55 °F Lab analysis ☐ Yes By _____
 Water quality concerns? ☐ Yes (describe below) _____

From	To	Description	Amount	Units

JAN 12 2009

(9) LOCATION OF WELL (legal description)
County Josephine Twp 35.00 S N/S Range 6.00 W E/W WM
Sec 9 ~~NE SW~~ 1/4 of the ~~SE NE~~ 1/4 Tax Lot 614
Tax Map Number _____ Lot _____
Lat _____ " or 42.54594700 42.54546 DMS or DD
Long _____ " or 122.40864800 -123.41589 DMS or DD
☒ Street address of well ☐ Nearest address ± 10'
526 HARTSFIELD LN MERLIN, OR 97532

(10) STATIC WATER LEVEL		Date	SWL(psi)	+	SWL(ft)
Existing Well / Predeepening					
Completed Well	09-18-2008				32
Flowing Artesian?		☐	Dry Hole?		☐

WATER BEARING ZONES				Depth water was first found 117	
SWL Date	From	To	Est Flow	SWL (psi)	+ SWL (ft)
09-18-2008	117	122	20		32

(11) WELL LOG		Ground Elevation	
Material	From	To	
Brown Decomposed Granite	0	41	
Dark Brown Decomposed Granite Soft	41	68	
Brown Decomposed Granite	68	87	
Brown & White Granite Med. Hard	87	129	
Grey Granite Hard	129	140	
<i>Amended by</i> <i>1/20/09</i> <i>1/2/09</i>			

Date Started 09-18-2008 Completed 09-18-2008

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1504 Date 09-18-2008
Electronically Filed
Signed CHARLIE GILL (E-filed)

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1835 Date 09-18-2008
Electronically Filed
Signed KEVIN D GILL (E-filed)
Contact Info (optional) Clouser Drilling LLC

WATER RESOURCES DEPT
TO THE SALEM, OREGON

THIS REPORT MUST BE SUBMITTED TO THE NEVADA REGIONAL WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK

Form Version: 0.88