

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

JOSE 60144

WELL I.D. LABEL# 116399
START CARD # 213716
ORIGINAL LOG #

(1) LAND OWNER
First Name Gary Last Name Boucher
Company P.O. Box 223
Address Wolf Creek State OR Zip 97497
(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrd
Casing: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐
Material From To Amt sacks/lbs
Seal: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)
Depth of Completed Well 300 ft.
BORE HOLE SEAL
Dia From To Material From To Amt (sacks/lbs)

10	0	18	Bentonite	0	18	9
6	18	300				Calculated 450 165

How was seal placed: Method ☒ A ☐ B ☐ C ☐ D ☐ E
☒ Other Dry Poured & Hydrated
Backfill placed from 0 ft. to 18 ft. Material Bentonite
Filter pack from 18 ft. to 300 ft. Material Gravel Size 20-40
Explosives used: ☐ Yes Type None Amount None

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount Pounds Actual Amount Pounds

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd

☒	☐	6	H	1	19	250	☒	☐	☒	
☐	☒	4	-	1	280	160	☐	☒	☐	

Shoe ☒ Inside ☒ Outside ☐ Other Location of shoe(s) 19
Temp casing ☐ Yes Dia 6 From 0 To 19

(7) PERFORATIONS/SCREENS
Perforations Method Lazer Cut
Screens Type PVC Material PVC
Perf/S Casing/ Screen Dia From To Scrn/slot width length # of slots Tel/ pipe size

☒	☐	4	280	300	20	2.75	3500	
-------------------------------------	--------------------------	---	-----	-----	----	------	------	--

(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian
Yield gal/min 1.5 Drawdown 280 Drill stem/Pump depth 1 hr
Temperature 53 °F Lab analysis ☐ Yes By Michael J. Pierce
Water quality concerns? ☐ Yes (describe below) TDS amount 160
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County Josephine Twp 33 N/S Range 6 E/W WM
Sec 11 NW 1/4 of the NE 1/4 Tax Lot 400
Tax Map Number 1240 Warner Rd Lot 400
Lat 42° 15' 10" N Long 122° 55' 10" W DMS or DD
☒ Street address of well ☐ Nearest address

1240 Warner Rd

(10) STATIC WATER LEVEL
Date 6/15/17 SWL(psi) 5.5 SWL(ft) 60
Existing Well / Pre-Alteration 5.5
Completed Well 5.5
Flowing Artesian? ☐ Dry Hole? ☐
WATER BEARING ZONES Depth water was first found 60
SWL Date From To Est Flow SWL(psi) + SWL(ft)

	60	65	1		55
	78	80	2		55

(11) WELL LOG
Ground Elevation 13
Material From To
Brown Clay 0 13
Gary Basalt 13 300

RECEIVED BY OWRD

JUL 14 2017

SALEM, OR

Date Started 6/14/17 Completed 6/15/17

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number 1251 Date 6/15/17
Signed Michael J. Pierce

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1251 Date 6/15/17
Signed Michael J. Pierce
Contact Info (optional)