

Corrected per WR

JUN 6 1991

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.
SALEM, OREGON

(START CARD) # W-20016

(1) OWNER:

Name Clark Roeder
Address 1717 Centennial #3
City Springfield State OR Zip 97477

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☐ Rotary Air ☒ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 412 ft.
Explosives used ☐ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
16"	0'	30'	cement	0	30	30 sacks
12"	30'	412'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from 30' ft. to 240' ft. Size of gravel Pea

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:				☐	☐	☐	☐
12"	+1	-239	250	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Factory
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
100'	240'	3/16 x3	1680	12"		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min Drawdown Drill stem at Time

750 200' 1 hr.

Pumped by Valley Pump.

Temperature of water 52° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other Surface

Depth of strata: 3'

(9) LOCATION OF WELL by legal description:

County Klamath Latitude _____ Longitude _____
Township 33S N or S, Range 7E E or W, WM.
Section 8 NE 1/4 NW 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) HWY 62
Fort Klamath

(10) STATIC WATER LEVEL:

34 ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 3'

From	To	Estimated Flow Rate	SWL
100'	406'	750	

(12) WELL LOG:

Material	From	To	SWL
Soil	0	3	
Brown Clay & Sand	3	9	
Blue Clay	9	26	
Sandy Blue Clay	26	41	
Sand & Gravel w/Clay	41	406	
Hard Grey Rock	406	412	
Clark Roeder didn't want to case the hole, wanted to find out if it had water. So he had the well test pumped. The bottom of the hole caved in and pumped sand. He didn't want to finish the well, and doesn't want to pay.			

Date started 8-16-90 Completed 5-21-91

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed John Phance WWC Number 693
Date 5-21-91