

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

RECEIVED

WATER WELL REPORT

APR 11 1972

STATE OF OREGON

KLAM

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date
of well completion.

STATE ENGINEER
SALEM OREGON

(Type type or print)

13058

(Do not write above this line)

State Well No.

39/10-9ca

State Permit No.

(1) OWNER:

Name Ralph McLeodAddress 5451 Walton Dr. Klamath Falls Oreg.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6" Diam. from 0 ft. to 61 ft. Gage 4 In.

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " "

" " "

Bailer test 20 gal./min. with 70 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 54° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite clay

Well sealed from land surface to 30 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal sacks

Number of sacks of bentonite used in well seal 3 sacks

Brand name of bentonite Quickjel

Number of pounds of bentonite per 100 gallons

of water 75 lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.Did any strata contain unusable water? ☒ Yes ☐ NoType of water? Surface depth of strata 5 Ft.Method of sealing strata off Casing & puddled clayWas well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Klam.

Driller's well number

N.E. ¼ S.W. ¼ Section 9 T. 39 S R. 10 E. W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 265 ft.

Static level 71 ft. below land surface. Date 3-24-72

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6 In.

Depth drilled 755 ft. Depth of completed well 755 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown sandy	0	4	-
Brown soft sandstone	4	12	
Brown wet Running sand	12	26	
Yellow sandy claystone	26	48	
Green claystone	48	265	
Approx. ½ G.P.M. 265			
Grey Claystone	265	305	
Green claystone	305	645	75
Grey claystone	645	670	75
Green claystone	670	685	
Grey sandy shale producing water			
gradually increasing to 20 g.p.m.			
	685	755	71

Work started 2 - 21 1972 Completed 3 - 24 - 1972

Date well drilling machine moved off of well 3 - 28 1972

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] James A. Roberts Date 4 - 10, 1972

(Drilling Machine Operator)

Drilling Machine Operator's License No. 184

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name James A. Roberts

(Person, firm or corporation)

(Type or print)

Address 148 East Main St. Klamath Falls, Oreg.

[Signed]

James A. Roberts

(Water Well Contractor)

Contractor's License No. 147 Date 4 - 10, 1972