

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy  
of this report are to be  
filed with the

STATE ENGINEER, SALEM, OREGON 97310  
within 30 days from the date  
of well completion.

WATER WELL REPORT  
STATE OF OREGON  
(Please type or print)  
(Do not write above this line)

RECEIVED  
SEP 28 1976  
State Well No. 395/11E-13bc  
State Permit No.

(1) OWNER:

Name Ted HARRIS  
Address 17400 VALERIO ST  
VAN NOYS, CALIF

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐  
Cable ☐ Jetted ☐  
Aug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐  
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

8 5/8" Diam. from +2 ft. to 55 ft. Gage 250  
" Diam. from 55 ft. to 250 ft. Gage 250  
" Diam. from 250 ft. to 250 ft. Gage 250

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

| Size of perforations | in. | by     | in. |
|----------------------|-----|--------|-----|
| perforations from    |     | ft. to | ft. |
| perforations from    |     | ft. to | ft. |
| perforations from    |     | ft. to | ft. |

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name  
Type Model No.  
Diam. Slot size Set from ft. to ft.  
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is  
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

gal./min. with ft. drawdown after hrs.  
AIR LIFT 200 GPM @ 144 " 2 "

Bailer test gal./min. with ft. drawdown after hrs.  
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used BENTONITE  
Well sealed from land surface to 54 ft.  
Diameter of well bore to bottom of seal 12 1/4 in.  
Diameter of well bore below seal 12 1/4 in.  
Number of sacks of cement used in well seal \_\_\_\_\_ sacks  
Number of sacks of bentonite used in well seal 10 sacks  
Brand name of bentonite AGUASANTA  
Number of pounds of bentonite per 100 gallons  
of water \_\_\_\_\_ lbs./100 gals.  
Was a drive shoe used? ☒ Yes ☐ No Plugs \_\_\_\_\_ Size: location \_\_\_\_\_ ft.  
Did any strata contain unusable water? ☐ Yes ☒ No  
Type of water \_\_\_\_\_ depth of strata \_\_\_\_\_  
Method of sealing strata off \_\_\_\_\_  
Was well gravel packed? ☐ Yes ☒ No Size of gravel: \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft.

(10) LOCATION OF WELL:

County KLAMATH Driller's well number  
SW 1/4 NW 1/4 Section 13 T. 39S R. 11E W.M.  
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 140 ft.  
Static level 48 ft. below land surface. Date 9/17/76  
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 7 7/8

Depth drilled 173 ft. Depth of completed well 173 ft.

Formation: Describe color, texture, grain size and structure of materials;  
and show thickness and nature of each stratum and aquifer penetrated,  
with at least one entry for each change of formation. Report each change in  
position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL                             | From | To  | SWL |
|--------------------------------------|------|-----|-----|
| BROWN SANDY TOPSOIL                  | 0    | 2   |     |
| SANDY YELLOW CLAY                    | 2    | 9   |     |
| HARD BROWN SANDSTONE                 | 9    | 20  |     |
| WHITE CLAY                           | 20   | 39  |     |
| GRAY CLAY                            | 37   | 54  |     |
| BLACK BASALT                         | 54   | 75  |     |
| HARD BROKEN GRAY BASALT              | 75   | 105 |     |
| HARD BLACK BASALT                    | 105  | 128 |     |
| HARD BLACK BASALT STREAKS BLUE SHALE | 108  | 140 |     |
| HARD GRAY & BLUE BROKEN              | 140  | 173 |     |

Work started 9/1/76 19 Completed 9/17/76 19  
Date well drilling machine moved off of well 9/17/76 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.  
Materials used and information reported above are true to my  
best knowledge and belief.

[Signed] Don M. Stone Date 9/23, 1976  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 656

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is  
true to the best of my knowledge and belief.

Name E.E. STOREY & SON WELL DRILLING INC  
(Person, firm or corporation) (Type or print)

Address 3847 HOPE KRAMERS, ORE

[Signed] Don M. Stone  
(Water Well Contractor)

Contractor's License No. 601 Date 9/23, 1976