

NOTICE TO WATER WELL CONTRACTOR:
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

STATE ENGINEER
SALEM, OREGON

STATE OF OREGON
(Please type or print)

STATE ENGINEER
SALEM, OREGON

State Well No. 39/11-36
State Permit No.

(1) OWNER:

Name J. C. Stevenson Jr.
Address Route 1, Box 104
Bonanza, Oregon

(2) LOCATION OF WELL:

County Driller's well number
1/4 1/4 Section 36 T. 39 R. 1 EAST W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☒ Other ☒

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☐

10" Diam. from 0 ft. to 12 ft. Gage 250
8 1/2" Diam. from 0 ft. to 20 ft. Gage .250
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☒ Yes ☐ No

Manufacturer's Name
Type Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite
Depth of seal 12 ft. Was a packer used? no
Diameter of well bore to bottom of seal 10 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 57' ft. below land surface Date 12/14/64
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Pump
Yield: 50 gal./min. with 90 ft. drawdown after 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well below casing

Depth drilled 362 ft. Depth of completed well 362 ft.

Formation: Describe by color, character, size of material and structure, and
show thickness of aquifers and the kind and nature of the material in each
stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top Soil	0	8
Reddish Brown Lava	8	11
Black Lava	11	21
Brown Lava Rock	21	24
Black Lava	24	40
Red & Black Lava	40	51
Black Lava Rock	51	92
Brown Lava	92	106
Black Lava	106	175
Black Lava	175	217
Black Lava	217	244
Red Lava	244	270
Black Lava	270	328
Black Lava	328	340
Black Lava	340	349
Black Lava (Real Hard)	349	361

Work started 11-14 19 64. Completed 12-14-64 19

Date well drilling machine moved off of well 12-14-64 19

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME Enloe Drilling Co.
(Person, firm or corporation) (Type or print)

Address Susanville, California

Drilling Machine Operator's License No. 342

[Signed] S. F. Enloe
(Water Well Contractor)

Contractor's License No. C 57 Date 1-4-71, 19