

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

KLAM 13681 WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 40.5/7E-1249

State Permit No. _____

(1) OWNER:

Name Dave Schreiber
Address P.O. Box 449 Keno, Ore. 97627

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Cable ☒
Driven ☐ Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

4" Diam. from +1 ft. to 43' ft. Gage 2.50
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations	in. by	in.
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		
perforations from _____ ft. to _____ ft.		

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? CONTRACTOR

Well: 18 gal./min. with 30 ft. drawdown after 6 hrs.

" " " " " "

Ballor test 10 gal./min. with 0 ft. drawdown after 2 hrs.

Artesian flow _____ g.p.m.

Temperature of water 56° Depth artesian flow encountered 370 ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 43 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 28 sacks
How was cement grout placed? pumped thru 1 1/4
INDUCTION TUBE

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☒ Yes ☐ No

Type of water? SHALLOW depth of strata 8'

Method of sealing strata off CASED & CEMENTED

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County KLAMATH Driller's well number _____

NE 1/4 NE 1/4 Section 12 T. 40 R. 7E W.M.

Bearing and distance from section or subdivision corner

Lot 1 Block 10 Whispering Pines

(11) WATER LEVEL: Completed well.

Depth at which water was first found 370 ft.

Static level 274 ft. below land surface. Date 4/30/80

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 421 ft. Depth of completed well 421 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil	0	3	
decomposed lava	3	8	
fractured lava surface	8	10	5'
water			
Brown lava	10	18	
loose brownish black lava	18	35	
hard gray black lava	35	50	
firm brownish black lava	50	133	
Brown claystone	133	161	
black decomposed lava	161	183	
hard blue gray basalt	183	198	
fractured grayish black lava	198	289	
firm brown lava	289	329	
Brown claystone	329	336	
Brown lava	336	345	
hard blue gray basalt	345	363	
red cinderous lava-water	363	370	274
blackish brown lava	370	421	

Work started 4/19 1980 Completed 4/30 1980

Date well drilling machine moved off of well 5/1 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Robert M. Powell Date 5/1, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 114

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Powell Well Drilling
(Person, firm or corporation) (Type or print)

Address P.O. Box 114 Keno, Ore.

[Signed] Robert M. Powell
(Water Well Contractor)

Contractor's License No. 454 Date 5/1, 1980