

WATER WELL REPORT
STATE OF OREGON

Klamath
14060

RECORDED
JUN 22 1982

State Well No. 395/8E-1bd
State Permit No.

WATER RESOURCES DEPT
SALEM, OREGON

(1) OWNER:

Name Ed Blodgett
Address 707 DeFatti Lane
City Klamath Falls State OR

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air Driven
Rotary Mud Dug
Cased Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other
Thermal: Withdrawal ReInjection

(5) CASING INSTALLED:

Steel Threaded Plastic Welded

14" Diam. from 14 ft. to 14 ft. Gauge 2.50
17" Diam. from 17 ft. to 78 ft. Gauge 2.50

(6) LINER INSTALLED:

" Diam. from " ft. to " ft. Gauge

(7) PERFORATIONS:

Perforated? Yes No

Type of perforator used
Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(8) SCREENS:

Well screen installed? Yes No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from " ft. to " ft.
Diam. Slot Size Set from " ft. to " ft.

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? Yes No If yes, by whom? Valley Pump
1300 gal/min. with 68 ft. drawdown after 2 hrs.
Air test 800 gal/min. with drill stem at 140 ft. 1 hrs.
Bailer test gal/min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered " ft.

(10) CONSTRUCTION:

Special standards: Yes No

Well seal—Material used Portland Cement
Well sealed from land surface to 78 ft.
Diameter of well bore to bottom of seal 18 in.
Diameter of well bore below seal 13 1/2 in.
Number of sacks of cement used in well seal 55 sacks
How was cement grout placed? Cement was mixed up.
1" pipe run down along side of pressure grouted in.
Was pump installed? NO Type HP Depth ft.
Was a drive shoe used? Yes No Plugs Size: location ft.
Did any strata contain unusable water? Yes No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? Yes No Size of gravel: ft.
Gravel placed from " ft. to " ft.

(11) LOCATION OF WELL:

County Klamath Driller's well number 02
SE 1/4 NW 1/4 Section 1 T. 39 S. R. 8 E W.M.
Tax Lot # Lot Blk Subdivision

Address at well location: North Farm where Orindale Rd. intersects 140

(12) WATER LEVEL: Completed well.

Depth at which water was first found 81 ft.
Static level 56 ft. below land surface. Date 5-28
Artesian pressure lbs. per square inch. Date

(13) WELL LOG:

Diameter of well below casing 13 1/2" to 14 1/2" then 6"

Depth drilled 540 ft. Depth of completed well 540 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown Topsoil	0	2	
Brown Lava Rock	2	14	
Brown Claystone with layers of lava	14	81	
Glacial Gravel w/B	81	76	
Brown Claystone	56	149	
Red Lava Rock w/B	149	163	
Gray Lava Rock	163	209	
Brown Lava Broken & w/B	209	226	
Gray Lava Rock	226	238	
Red Lava Broken & w/B	238	286	
Gray Claystone	286	428	
Black Lava Rock	428	511	
Red Lava Broken & w/B	511	578	
Black Lava Rock with streaks of Gray Claystone	578	540	

Work started 4-29 1982 Completed 5-28 1982
Date well drilling machine moved off of well 5-28 1982

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Adellebert R. Clark Date 5-28 1982
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1476

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Name Adellebert R. Clark - Clark Well Drilling
(Person, firm or corporation) (Type or print)

Address Rt. 2, Box 592, P. Chilloguich, OR

[Signed] Adellebert R. Clark
(Water Well Contractor)

Contractor's License No. 805 Date 5-28 1982