

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM 10, OREGON
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

State Well No. 40/12-7 D

State Permit No.

(1) OWNER:

Name **Lloyd D. Cogley**
Address **Rt. 1 Box 787**
Klamath, Falls, Oregon

(2) LOCATION OF WELL:

County **Klamath** Driller's well number
1/4 NW 1/4 Section 7 T. 40S R. 12E W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐ Rotary ☐ Driven ☐
Irrigation ☒ Test Well ☐ Other ☐ Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(5) TYPE OF WELL:

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
16" Diam. from 0 ft. to 19 ft. Gage 1"
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name
Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal **Cement**
Depth of seal **19** ft. Was a packer used? **No**
Diameter of well bore to bottom of seal in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level **30** ft. below land surface Date **3/30/65**
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level **Interstate pump co.**
Was a pump test made? ☒ Yes ☐ No If yes, by whom?
Yield: **950** gal./min. with **120** ft. drawdown after **4** hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water **59** Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing **16 1/2**
Depth drilled **702** ft. Depth of completed well **702** ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
soil	0	1/2
decomposed lava & clay	1/2	23
decomposed black lava & clay	23	52
brown shale & green clay	52	55
black shale	55	68
brown shale & green clay	68	85
black shale	85	140
brown shale	140	173
dark brown shale & clay	173	181
green clay & black shale	181	214
black lava and blue clay	214	237
brown shale & blue clay	237	244
black lava & blue clay	244	296
yellow clay & brown shale	296	310
brown shale & yellow clay	310	410
green sandstone	410	486
brown shale	486	510
green sandstone	510	515
hard gray green shale	515	603
yellow clay & black shale	603	610
gray shale & green mud	610	630
brown & gray shale	630	644
brown shale	644	702

Work started **2/18** **1965** Completed **3/30** **1965**
Date well drilling machine moved off of well **3/30** **1965**

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME **John A. Van Meter**
(Person, firm or corporation) (Type or print)
Address **P.O. Box 204 Malin, Oregon**

Drilling Machine Operator's License No. **118**[Signed] **John A. Van Meter**
(Water Well Contractor)Contractor's License No. **170** Date **4/4** **65**

(USE ADDITIONAL SHEETS IF NECESSARY)