

WATER WELL REPORT
STATE OF OREGON

RECEIVED

MAY 9 1984

State Well No.

365/10E-12cb

WATER RESOURCES DEPT.
SALEM, OREGON

State Permit No.

(1) OWNER:

Name WINFORD MAUER
Address 2412 PINE GROVE RD.
City KLAMATH FALLS State ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal ☐ Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6 5/8" Diam. from +1 1/2 ft. to 5 1/2 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

id. gal./min. with ft. drawdown after hrs.
" " " " "
Air test 25 gal./min. with drill stem at 60 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water 54 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used CEMENT
Well sealed from land surface to 40 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 8 TO 5 1/2 in.
Number of sacks of cement used in well seal 10 + 5 1/2 BENT sacks
How was cement grout placed? PUMPED

Was pump installed? NO Type HP Depth ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☒ Yes ☐ No
Type of Water? SURFACE depth of strata 49'
Method of sealing strata off CEMENT & CASING
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County KLAMATH Driller's well number
NW 1/4 SW 1/4 Section 12 T. 36 S R. 10 E W.M.
Tax Lot # Lot 7 Blk 28 Subdivision
Address at well location: KLIMROD PARK
LOT 7 BLK 28

(11) WATER LEVEL: Completed well.

Depth at which water was first found 128 ft.
Static level 15 ft. below land surface. Date 5/4/84
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 138 ft. Depth of completed well 138 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
BROWN SANDY SOIL	0	4	
BROWN CHALK	4	13	
CONGLOMERATE	13	15	
GRAY CLAY	15	25	
GRAY SHALE	25	81	
GRAY SHALE & STRKS SAND	81	87	
BROWN LOAM	87	89	
GRAY SHALE	89	101	
GREEN SHALE	101	107	
GRAY SHALE	107	110	
BLACK SANDSTONE	110	115	
GRAY SHALE	115	128	
GREEN SHALE & STRKS SAND	128	135	
BLACK SANDSTONE	135	136	
GREEN SHALE & STRKS	136	138	
OF SAND,			

Work started 5/3/84 Completed 5/4/84
Date well drilling machine moved off of well 5/4/84

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Robert D. Rose Date 5-7-1984
(Drilling Machine Operator)

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Name E.E. STOFFEY & SON WELL DRILLING INC.
(Person, firm or corporation) (Type or print)
Address 3847 HOPKINS FALLS, ORE
[Signed] E.E. Stoffey
(Water Well Contractor)
Contractor's License No. 14 Date 5/6/84, 19

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690