

WATER WELL REPORT
STATE OF OREGON

KLAM
2085

RECEIVED State Well No. 365/12E-23.d

OCT 29 1981

State Permit No.
WATER RESOURCES DEPT
SALEM, OREGON

(1) OWNER:

Name Joe Albee
Address P.O. Box 84-A
City Beatty, Oregon 97621 State

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
Cased ☐ Bored ☐ Thermal ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
16" Diam. from +1 ft. to 91 1/2 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge
(6) PERFORATIONS: Perforated? ☐ Yes ☒ No
Type of perforator used none
Size of perforations none in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No. If yes, by whom? Valley Pump Co.
Yield: 3300 gal./min. with 30 ft. drawdown after 4 hrs.
Air test gal./min. with drill stem at ft. hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 56 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒
Well seal—Material used Cement
Well sealed from land surface to 90 ft.
Diameter of well bore to bottom of seal 20 in.
Diameter of well bore below seal 16 in.
Number of sacks of cement used in well seal 46 sacks
How was cement grout placed? Pumped from the bottom of the seal, up to the ground surface.
2 sacks of bentonite also used.
Was pump installed? NO Type HP Depth ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? none depth of strata none
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: none
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Klamath Driller's well number
N 1/2 SE 1/4 Section 23 T. 36S R. 12 E. W.M.
Tax Lot # Lot Blk Subdivision
Address at well location: Ranch near Beatty Or.

(11) WATER LEVEL: Completed well.

Depth at which water was first found 67 ft.
Static level 64 ft. below land surface. Date 9, 29, 81
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 16"
Depth drilled 350 ft. Depth of completed well 350 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil & boulders	0	3	
Brown clay & gravel	35	8	
Brown sandstone	8	67	
Black sandstone	67	88	64'
Brown claystone	88	92	
Brown rock	92	96	
Grey rock	96	103	64'
Brown lava rock	103	110	64'
Grey rock	110	145	64'
Brown lava rock, light in color	145	173	
Soft light brown rock	173	197	
Black lava rock	197	212	64'
Tan pumice	212	295	64'
Brown lava rock	295	350	64'

Work started 9, 16, 19 81 Completed 9, 29, 19 81
Date well drilling machine moved off of well 9, 29, 19 81

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Stephen R. Hughes Date 10, 27, 19 81
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1171

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Name Norm Sevey Well Drilling, Inc.
(Person, firm or corporation) (Type or print)
Address 800 Old Midland Rd. Klamath Falls, OR 97601
[Signed] Norm Sevey
(Water Well Contractor)
Contractor's License No. 408 Date 10, 27, 19 81

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690