

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

RECEIVED

MAR 8 1962 WATER WELL REPORT

STATE OF OREGON ENGINEER (Please type or print)

Con Flynn & Sons

KLAM 2088

36/12-23F(1)

G-4465 G2174

State Well No.

State Permit No.

(1) OWNER:

Name J.L. Stephens & Patty Stephens
Address Beatty Oregon

(2) LOCATION OF WELL:

County Klamath Driller's well number
1/4 Section T. R. W.M.

Bearing and distance from section or subdivision corner

The well or other source is located
1320 ft S and 1330 ft E from the Sec.
corner of 15,14,22,23 of T.36S R.12 E.

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

12" Diam. from 0 ft. to 80 ft. Gage 188
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name
Model No.
Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal NA Cement
Depth of seal 80 ft. Was a packer used? No
Diameter of well bore to bottom of seal 12 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 8 ft. below land surface Date 2-27-62
Artesian pressure None lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?
Yield: 1275 gal./min. with 72 ft. drawdown after 1 hrs.
" 1075 " 60 " 1 "
" 1275 " 72 " 1 "
Baller test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m. Date
Temperature of water 52 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 12"

Depth drilled 520 ft. Depth of completed well 520 ft.
Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top Soil	0	3
Hard Pan (yellow)	3	5
Clay Blue	5	30
Sand Black (fine)	30	35
Clay (blue)	35	90
Sand (black)	90	92
Clay (chalk) w		
Small layers of Sand	92	480
Pumice	480	485
Brown Clay	485	489
Red and Black Sindens	489	520

Work started Oct 1 1961 Completed Mar 6 1962
Date well drilling machine moved off of well Mar 6 1962

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Jerry L. Stephens (Type or print)

Address PO Box 33 Beatty Ore

Drilling Machine Operator's License No.

[Signed] Jerry L. Stephens (Water Well Contractor)

Contractor's License No. Date , 19