

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM 10, OREGON
within 30 days from the date
of well completion.

WATER WELL REPORT

JAN 7 1965 STATE OF OREGON
(Please type or print)

G-4122

State Well No.

State Permit No.

(1) OWNER:

Name WILLIAM CRESWELLAddress 7809 DONEGAL
KLAMATH FALLS, ORE.

(2) LOCATION OF WELL:

County KLAMATH Driller's well numberSE 1/4 NE 1/4 Section 32 T. 38S R. 8E W.M.

Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐Cable ☒ Jetted ☐Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

" Diam. from ft. to ft. Gage

20 " Diam. from +2 ft. to 57 1/2 ft. Gage 281

" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.

..... perforations from ft. to ft.

..... perforations from ft. to ft.

..... perforations from ft. to ft.

..... perforations from ft. to ft.

..... perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

..... Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal BENTONITEDepth of seal 57 ft. Was a packer used? NODiameter of well bore to bottom of seal 24 in.Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☒ Yes ☐ NoWas well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? Depth of strata

Method of sealing strata off

(10) WATER LEVELS:

Static level 140 ft. below land surface Date 12/7/64

Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? PALEY PUMP

Yield: gal./min. with ft. drawdown after hrs.

" 2050 " 58 " 3 "

" " " "

Ball test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 57 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 20Depth drilled 604 ft. Depth of completed well 604 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL

FROM

TO

REFER TO SHEETS ATTACHED (2)Work started 7/28/64 Completed 12/12/64 19Date well drilling machine moved off of well 12/12/64 19

(13) PUMP:

Manufacturer's Name


Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME E E STOREY
(Person, firm or corporation) (Type or print)Address 3831 Hope KLAMATH FALLS OREDrilling Machine Operator's License No. 1154107[Signed] E E STOREY
(Water Well Contractor)Contractor's License No. 74 Date 1/2/64, 19

(USE ADDITIONAL SHEETS IF NECESSARY)



G-4122

E. E. STOREY

Well Drilling

TUxedo 4-3990

3831 Hope Street

KLAMATH FALLS, OREGON



RECEIVED
JAN 7 1965


WILLIAM CRISWELL
LONG LAKE RANCH
KLAMATH FALLS, OREGON

Started 7/28/64

Finished 12/12/64

LOG

0	-	2	top soil
2	-	4	small boulders and clay
4	-	8	hardpan
8	-	30	yellow clay
30	-	55	brown clay
55	-	67	brown lava
67	-	88	gray basalt
88	-	97	brown lava
97	-	103	brown shale
103	-	131	brown lava
131	-	134	gray basalt
134	-	151	brown lava
151	-	159	gray basalt
159	-	160	coarse gravel, water flow
160	-	190	gray basalt
190	-	205	brown lava
205	-	312	gray basalt
312	-	320	gray shale
320	-	372	gray basalt
372	-	379	blue basalt
379	-	399	gray basalt
399	-	403	broken gray basalt, no water
403	-	451	gray basalt
451	-	458	gray shale
458	-	468	gray basalt
468	-	497	very brown lava
497	-	501	black sandstone
501	-	510	brown lava
510	-	521	brown shale
521	-	545	brown lava
545	-	547	broken gray basalt
547	-	555	gray basalt
555	-	556	broken gray basalt
556	-	604	gray basalt



E. E. STOREY
Well Drilling

TUxedo 4-3990
3831 Hope Street
KLAMATH FALLS, OREGON

WILLIAM CRESWELL
LONG LAKE RANCH
KLAMATH FALLS, OREGON

G-4122

38/8-33P
Klamath



LOG -- continued

Static water level 140'

Temperature 57 degrees

Pumped 2,050 GPM @ 198'

1,000 GPM @ 166'

Reduced bore at 330' to 16"

Installed 59' 8" - 20" od X .281

Set at 57' 6", rolled show

Sealed with Bentonite

Caving at 559'