


SEP 1 0 1998

WATER RESOURCES
SALEM, OREGON

STOREY DRILLING SERVICES

P.O. Box 98 • MIDLAND, OREGON 97634
 (541) 884-3990 • (800) 245-8122
 Fax #: (530) 528-2562
 22580 ADOBE ROAD • RED BLUFF, CALIFORNIA 96080
 CONTRACTOR'S LICENSES:
 OR #601 • CA #583153 • NV #38199



Mr. Tom Griffith
 Griffith & Parker
 4583 King Road
 Williams, California 95987

START: JUNE 29, 1998
 FINISH: AUGUST 25, 1998

WELL LOCATION: Approximately 3 miles northwest of Sprague River, Oregon
 SE¼ NE¼ S30 T35S R10E

LOG

0 - 7	Sandy clay topsoil with medium boulders
7 - 12	Brown sandstone
12 - 19	Sticky yellow clay
19 - 56	Grey clay
56 - 95	Green shale with streaks of black sandstone
95 - 246	Green clay
246 - 260	Green shale
260 - 509	Green clay
509 - 602	Hard green shale
602 - 662	Green shale
662 - 794	Green clay
794 - 824	Green shale
824 - 826	Hard mud stone
826 - 855	Black basalt
855 - 897	Sticky grey clay
897 - 962	Sticky grey clay with streaks shale
962 - 1022	Hard black basalt
1022 - 1024	Green clay
1024 - 1030	Broken black basalt
1030 - 1047	Hard black basalt
1047 - 1066	Hard grey basalt
1066 - 1080	Sticky grey clay
1080 - 1092	Sticky black clay
1092 - 1097	Brownish red lava with streaks red cinders
1097 - 1112	Sticky black clay
1112 - 1146	Soft decomposed brown lava with streaks clay
1146 - 1166	Sandy black clay
1166 - 1169	Brown sandstone
1169 - 1170	Sticky brown clay
1170 - 1189	Green clay
1189 - 1207	Brown shale & clay
1207 - 1298	Pumice with streaks black rock
1298 - 1325	Sticky brown clay


RECEIVED

SEP 10 1983

WATER RESOURCES DEPT.
SALEM, OREGON

STOREY DRILLING SERVICES

P.O. Box 98 • MIDLAND, OREGON 97634
(541) 884-3990 • (800) 245-8122
Fax #: (530) 528-2582
22560 ADOBE ROAD • RED BLUFF, CALIFORNIA 96080
CONTRACTOR'S LICENSES:
OR #601 • CA #583153 • NV #38199



PAGE 2

WELL LOCATION: SE¼ NE¼ S30 T35S R10E

LOG (continued)

1325 - 1374	Sticky grey clay
1374 - 1388	Sticky green clay
1388 - 1452	Sticky black clay with streaks black shale
1452 - 1482	Black sandstone with streaks clay
1482 - 1492	Brown lava
1492 - 1636	Sticky black clay with streaks hard shale
1636 - 1669	Sticky black clay with streaks black sandstone

22 feet of 16 inch O. D. x .250 wall steel casing set at 21 feet with no drive shoe.

8 3/4 inch diameter hole drilled from 21 feet to 1669 feet.

Airlifted 30 gallons per minute at 360 feet. Static water level at 17 feet.

Final finished depth of well unknown due to squeezing hole conditions - casing needed to keep hole open to 1669 feet.