

Dan Raines
 cased 14" 20' deep.

14" well

1 WP 405 N. 11 E
 Sec 25 NE 4 NW

1924?

0-1	Topsail + small boulders	961-1005	Bm Sticky Shale
1-4	Hardpan	1005-1012	{ Hard Bm + gray shale gray lava
4-7	Bm clay + sand	1012-1015	gray lava
7-8	gray boulders	1015-1026	Sticky Bm Shale
8-9	Bm clay + sand	1026-1077	hard gray lava
9-27	Bm clay	1077-1097	" " shale
27-33	Blk Sandstone	1097-1148	Boulders + clay
33-42	gray boulders + clay		
42-44	yellow clay	0-20'	18"
44-154	gray boulders + clay	20-200'	16"
154-192	yellow shale	200-300	14"
192-237	gray lava	300-400	12"
237-245	Bm clay + Basalt	400-1000	10"
245-354	gray basalt + layers Sandstone	1000-1148	8"
354-400	gray lava		
400-506	gray Basalt		
506-508	green clay		
508-579	hard green shale		
579-589	gray + Bm lava		
589-748	green + gray Shale		
748-765	green shale		
765-769	gray shale		
769-805	hard gray basalt		
805-864	gray shale		
864-920	Layers gray basalt + gray shale		
920-961	gray shale		