

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537765)

KLAM 54852 WELL ID # 4100

(START CARD) # 166768

(1) OWNER

BRYAN OKSEN

2609 BERKLEY ST.

KLAMATH FALLS WATER RESOURCES DEPT
SALEM, OREGON 97601

RECEIVED
MAY 19 2005
MAY 19 2005

05 13

(2) TYPE OF WORK : NEW WELL

(3) DRILL METHOD : ROTARY AIR

(4) PROPOSED USE: Domestic

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO..... Depth of Completed Well 181..... ft.

Explosives used NO..... Type..... Amount.....

HOLE		SEAL		AMOUNT	
Diameter	From To	Material	From To	Sacks	
10"	0 79	BENTONITE	0 36	15	
6"	79 181	CEMENT	36 79	10	

How was seal Placed POURED DRY & C

Backfill placed from..... ft. to..... ft. Material.....

Gravel placed from..... ft. to..... ft. Size of Gravel.....

(6) CASING / LINER:

Dia.	From To	Gage	Material
CASING 8"	+1 79	250	STEEL / WELDED

Final location of shoe (s) 79'

(7) PERFORATIONS / SCREENS:

METHOD	TYPE	MATERIAL
--------	------	----------

From To Slot size Number Dia. Tele / pipe size

(8) WELL TESTS:

Minimum testing time is 1 hour

TESTING METHOD AIR

Yield GPM Drawdown Drill stem at Time

46..... 75..... 1 HOUR

25..... 60..... 1 HOUR

Temperature of Water 60 F° Depth Artesian Flow Found.....

Was a water analysis done? NO..... By whom.....

Did any strata contain water not suitable for intended use? NO.....

(9) LOCATION OF WELL by legal description :

County KLAMATH..... Latitude..... Longitude.....

Township 39..... S..... Range 8..... E.....

Section 22..... SW 1/4..... NE 1/4.....

Tax Lot 4500..... Lot..... Block..... Subdivision.....

Street Address of Well (or nearest address)

6509 SCOTTS BLUFF RD. KLAMATH FALLS

(10) STATIC WATER LEVEL:

44 ft. below land surface Date April 29, 2005

Artesian pressure..... Date.....

(11) WATER BEARING ZONES :

Depth at which water was first found 110.....

From	To	Estimated Flow Rate	SWL
110	181	80 GPM	44

(12) WELL LOG:

Ground Elevation

	FROM	TO	SWL
SOIL	0	7	
BROWN CLAY	7	14	
LIGHT BROWN CLAY	14	29	
BLUE CLAY	29	49	
GREY BASALT	49	55	
BROWN & GREY CLAYSTONE	55	67	
GREY & BROWN BASALT	67	110	
BROWN & RED CINDERS	110	119	44
BROWN & GREY BASALT	119	181	44

Date started April 26, 2005

Completed April 29, 2005

(Unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

[Signature] DATE 5-18-05 WWC # 1452

(Bonded) Water Well Constructor Certification: I accept responsibility for the construction alteration or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

[Signature] DATE 5-18-05 WWC # 693

1949-50

[illegible]

SECTION 22 T38S. R40E. W4M,
CLATSOP COUNTY

