

KLAM 55462

KLAM
55462

WELL ID # L 73156

(START CARD) # 146860

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form

(1) OWNER:

Well Number:

Name Dean & Jerry Wells
Address 24201 South Pole Valley Rd.
City Klamath Falls State OR Zip 97603

(2) TYPE OF WORK:

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 420 ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Amount	
Diameter	From	To	Material	From	To	sacks or pounds	
12"	0	19	Benbrite	0	19	12 Sacks	
8"	19	420					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E☒ Other Poured

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8"	4'	19'	.250	☒	☐	☒	☐
Liner:					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

		Method		Material	
		Type			
From	To	Slot size	Number	Diameter	Tele/pipe size
					Casing
					Liner

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailor ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
25		420'	1 hr.

Temperature of Water 63° Depth Artesian Flow foundWas a water analysis done? ☐ Yes By whomDid any strata contain water not suitable for intended use? ☐ Too little☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Klamath Latitude Longitude
Township 39S N or S. Range 11.5 E E or W. of WM.
Section 35 NW/4 NE 1/4
Tax lot 500 Lot Block Subdivision
Street Address of Well (or nearest address) 24201 South Pole Valley Rd. K-Falls

(10) STATIC WATER LEVEL:

23 ft. below land surface. Date 6-12-06
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 248'

From	To	Estimated Flow Rate	SWL
248'	251'	105 gal/min	23
382'	400'	155 gal/min	23

(12) WELL LOG:

Ground elevation

Material	From	To	SWL
Top Soil	0	3	
White g/k Rock	3	32	
Grey Clay	32	125	
Grey Clay Stone	125	248	
Fractured Clay Stone	248	382	23
Fractured Clay Stone	382	420	23

RECEIVED

JUL 07 2006

WATER RESOURCES DEPT
SALEM, OREGON

RECEIVED

OCT 25 2006

WATER RESOURCES DEPT
SALEM, OREGONDate started 6-11-06 Completed 6-12-06

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed David Wiley WWC Number 1863
Date 6-30-06