

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.745)

Instructions for completing this report are on the last page of this form.

WELL ID. # 88638
START CARD # W191274

(1) LAND OWNER Seramic Jennings Well Number _____
Name P.O. Box 7377
Address Bend State OR Zip 97708

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/condition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 75 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

SOLE SEAL
Diameter From To Material From To Sacks or pounds
10" 0 20 Bentonite 0 20 12 sacks
6" 20 75 _____

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other pouring Dry

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from 70 ft. to 75 ft. Size of gravel 8X12

(6) CASING/LINER:

Casing	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
☒	6"	0	70	1250	☒	☐	☒	☐
☐					☐	☐	☐	☐
☐					☐	☐	☐	☐
☐					☐	☐	☐	☐
☐					☐	☐	☐	☐
☐					☐	☐	☐	☐
☐					☐	☐	☐	☐
☐					☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Torch
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Title/pipe size	Casing	Liner
60	70	6"	36	1/8"	6"	☒	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump	☐ Bailor	☐ Air	☐ Artesian
Yield gpm	Drawdown	Drift stem at	Flowing time
17	15 ft.		1 hr.

Temperature of water 44° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too Salty

☐ Salty ☐ Muddy ☐ Other ☐ Other ☐ Other

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Klamath Latitude _____ Longitude _____
Township 23 N of S Range 10 E or W. W.M.
Section 36B 1/4 NW 1/4 NW
Tax Lot 3700 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Across the street from 144936 Gracewood Pl

(10) STATIC WATER LEVEL:

48 ft. below land surface. Date 5-16-07
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 48 ft.

From	To	Estimated Flow Rate	SWL
48 ft.	75 ft.	7 GPM	48 ft.

(12) WELL LOG:

Ground Elevation 4,000 ft

Material	From	To	SWL
Pumpe top so. 1	0	5'	
BDN Sand & clay	5'	23'	
BDN sand	23'	31'	
Grey Ash & B/K sand	31'	48'	48'
Black sand	48'	59'	48'
Small Gravel mixed	59'	70'	48'
with Black sand	70'		48'
Black sand		75'	48'

RECEIVED

MAY 21 2007

WATER RESOURCES DEPT
SALEM OREGON

Date started 5-15-07 Completed 5-16-07

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1761
Signed Richard Buzeln Date 5-18-07