

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 85914
START CARD # W 191905

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER John Thies Well Number _____
Name John Thies
Address 1728 Regor
City LaPine State OR Zip 97739

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 45 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
10"	0'	18'	Bent	0'	18'	850# Sacks
6"	18'	45'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Poured

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	41'	30'	1250	☒	☐	☒	☐
Liner:	4 1/2"	3'	45'	SDR 26	☐	☒	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS
☒ Perforations Method Saw cut
☒ Screens Type Tele Material PVC

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
25'	45'	2"	5640	1010	4 1/2"	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
150 PM	6'		1 Hr

Temperature of water 46° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)

County Klamath
Tax Lot 6200 Lot _____
Township 23 N or S Range 9 E or W WM
Section 24B 1/4 _____ 1/4 _____

Lat 43° 34' 205 or _____ (degrees or decimal)
Long 121° 35' 979 or _____ (degrees or decimal)

Street Address of Well (or nearest address) _____

(10) STATIC WATER LEVEL

10' ft. below land surface. Date 6-27-07

_____ ft. below land surface. Date _____

Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found 28'

From	To	Estimated Flow Rate	SWL
28'	45'	150 PM	10'

(12) WELL LOG

Ground Elevation 4312

Material	From	To	SWL
Pumice	0'	4'	
Clay & large Gravel	4'	16'	10'
Brown Clay	16'	24'	
Fine Sand	24'	26'	
Coarse Sand & Gravel	26'	45'	

RECEIVED

JUL 18 2007

WATER RESOURCES DEPT
SALEM, OREGO

Date Started 6-26-07 Completed 6-27-07

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date 6-27-07

Signed Charles Tamm

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1842 Date 6-27-07

Signed Charles Tamm