

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 82486
START CARD # 167229

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name J.R. Baughman
Address PO Box 1054
City Lapine State Or. Zip 97759

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 53 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE		SEAL		Materials		Sacks or pounds	
Diameter	From	To	From	To			
10"	0	18		0	18		
6"	18	53				14	sacks

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other Poured.
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 6" 0 18 41 250 ☒ ☐ ☒ ☐
Liner: 4" 23 43 160 ☐ ☒ ☐ ☐
Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
☐ Perforations Method Sawrd.
☒ Screens Type Factory Material PVC.
From To Slot size Number Diameter Tele/pipe size Casing Liner
43 53 10000 2640 4" ☐ ☒

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Artesian
Yield gal/min Drawdown Drill stem at Time
30 4' 1 hr

Temperature of water 47° Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Klamath Latitude _____ Longitude _____
Township 23 S N or S Range 10 E or W. WM.
Section 18 NW 1/4 SW 1/4
Tax Loc 00300-0000 Block _____ Subdivision _____
Street Address of Well (or nearest address) 149204 Hwy 97 N.

(10) STATIC WATER LEVEL:
11 ft. below land surface. Date 6-18-07
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 4'

From	To	Estimated Flow Rate	SWL
<u>4</u>	<u>29</u>	<u>?</u>	<u>4</u>
<u>41</u>	<u>53</u>	<u>50</u>	<u>11</u>

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
<u>Soil Brown</u>	<u>0</u>	<u>1</u>	
<u>Pumice Brown</u>	<u>1</u>	<u>4</u>	
<u>Sand + Gravel Brown</u>	<u>4</u>	<u>30</u>	<u>4</u>
<u>Clay Grey</u>	<u>30</u>	<u>41</u>	
<u>Sand + Gravel Brown</u>	<u>41</u>	<u>53</u>	<u>11</u>

RECEIVED

JUL 25 2007

WATER RESOURCES DEPT
SALEM OREGON

Date started 6-15-07 Completed 6-18-07

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
WWC Number 1820
Signed Tom Sted Date 6-18-07