

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 85916

START CARD # W 191907

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Dwight Panton Well Number _____
Name Dwight Panton
Address P.O. Box 2573
City Lafre State OR Zip 97739

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 80 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
10"	0'	18'	Best	0'	18'	9.50 Sacks
6"	18'	80'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Poured
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER
Casing: Diameter From To Gauge Steel Plastic Welded Threaded
6" 4' 60' 1.250 ☒ ☐ ☒ ☐
Liner: 1 1/2" 20' 80' SDR 26 ☐ ☒ ☐ ☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS
☒ Perforations Method Saw Cut
☒ Screens Type Tele Material PVC
From To Slot Number Diameter Tele/pipe Casing Liner
60' 80' 2" 5640 1.010 4 1/2" ☐ ☒

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
Yield gal/min 156 Pm Drawdown 2' Drill stem at _____ Time 1 Hr 30 min

Temperature of water 46° Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL (legal description)
County Clatsop
Tax Lot 1100 Lot _____
Township 23 N or S Range 10 E or W WM
Section 35B 1/4 _____ 1/4 _____

Lat 43° 32' 479" or _____ (degrees or decimal)
Long 121° 29' 852" or _____ (degrees or decimal)

Street Address of Well (or nearest address)
10894 Rider Ct.
10338

(10) STATIC WATER LEVEL
44 ft. below land surface. Date 8-13-07
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES
Depth at which water was first found 60'
From To Estimated Flow Rate SWL
60' 80' 15 GPM 44'

(12) WELL LOG Ground Elevation _____
Material From To SWL
Pumice 0' 4' _____
Clay Soil 4' 10' _____
Brown Clay 10' 57' _____
Pumice 57' 59' _____
Coarse Sand & Gravel 59' 62' 44'
Coarse Sand 62' 80' _____
RECEIVED
SEP 17 2007
WATER RESOURCES DEPT
SALEM, OREGON

Date Started 8-7-07 Completed 8-12-07

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1842 Date 8-12-07

Signed Charles Jensen