

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L 85917

START CARD # W 191908

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Shirley Leaton Well Number _____
Name _____
Address P.O. Box 2151
City LAPINE State OR Zip 97739

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 50 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
10"	0'	18'	Bent	0'	18'	850 Sacks
6"	18'	50'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Poured

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	41'	30'	.250	☒	☐	☒	☐
Liner: 4 1/2"	18'	50'	SDR 26	☐	☒	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS
☒ Perforations Method Saw Cut
☒ Screens Type Take Material PVC

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
30'	50'	2"	5640	.010	4 1/2"	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
156 Pm	5'		1 Hr

Temperature of water 43° Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL (legal description)
County Klamath
Tax Lot 2700 Lot _____
Township 23 N or S Range 10 E or W WM
Section 16 A 1/4 _____ 1/4 _____
Lat 43° 32.479" or _____ (degrees or decimal)
Long 121° 29.852" or _____ (degrees or decimal)

Street Address of Well (or nearest address)
150375 Midstate RD.

(10) STATIC WATER LEVEL
18' ft. below land surface. Date 9-30-07
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES
Depth at which water was first found 30'

From	To	Estimated Flow Rate	SWL
30'	50'	15 GPM	18'

(12) WELL LOG Ground Elevation 4310'

Material	From	To	SWL
Pumice	0'	3'	
Clay Soil	3'	10'	
Clay	10'	19'	
Coarse Sand & Gravel	19'	25'	18'
Clay	25'	30'	
Fine Sand & Gravel	30'	43'	
Fine black Sand	43'	50'	

RECEIVED
OCT 03 2007
WATER RESOURCES DEPT
SALEM, OREGON

Date Started 9-30-07 Completed 9-30-07

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1842 Date 9-30-07

Signed Charles Trench