

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON within 30 days from the date of well completion.

RECEIVED KLAMATH JUN 8 1965 WATER WELL REPORT JUN 10 1965 STATE ENGINEER SALEM OREGON

State Well No. 29/7-12 Permit No.

(1) OWNER: Cecil P. Pettit, Box 10 Chemult, Ore

(2) LOCATION OF WELL: County Klamath, Driller's well number 12, Section 7 E, W.M. 7 E

(3) TYPE OF WORK (check): New Well [X], Deepening [], Reconditioning [], Abandon []

(4) PROPOSED USE (check): Domestic [X], Industrial [], Municipal [], Irrigation [], Test Well [], Other []

(6) CASING INSTALLED: 6 3/4" Diam. from 0 ft. to 135 ft. Gage 1/4"

(7) PERFORATIONS: Type of perforator used TORCH, Size of perforations 3/16 in. by 4 in., perforations from 70 ft. to 130 ft.

(8) SCREENS: Well screen installed? [X] No, Manufacturer's Name PERFORATED PIPE, Slot size 1/8", Set from 70 ft. to 130 ft.

(9) CONSTRUCTION: Well seal—Material used in seal CEMENT, Depth of seal 30 ft., Diameter of well bore to bottom of seal 12 in., Were any loose strata cemented off? [X] No

(10) WATER LEVELS: Static level 61 ft. below land surface, Artesian pressure lbs. per square inch

(11) WELL TESTS: Drawdown is amount water level is lowered below static level, Yield: 25 gal./min. with 0 ft. drawdown after 2 hrs.

Bailer test gal./min. with ft. drawdown after hrs., Artesian flow g.p.m. Date, Temperature of water Was a chemical analysis made? [X] Yes [] No

(12) WELL LOG: Diameter of well below casing 6", Depth drilled ft., Depth of completed well ft., Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

Table with columns MATERIAL, FROM, TO. Entries include POMICE 0-50, HARD gray shale 56-73, water bearing sand 73-135.

Work started 5/8 1965 Completed 5/17 1965, Date well drilling machine moved off of well 11/14 19

(13) PUMP: Manufacturer's Name REDA, Type SUBMER, H.P. 1/2

Water Well Contractor's Certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. NAME ROY W POWELL, Address HEND OME Box 123, Drilling Machine Operator's License No. 114, [Signed] ROY W POWELL, Contractor's License No. 210 Date 5/20 1965