

STATE OF OREGON WATER SUPPLY WELL REPORT

KLAM 62344

WELL I.D. LABEL# L 154512 START CARD # 1078182 ORIGINAL LOG #

2/1/2026

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

(1) LAND OWNER Owner Well I.D. First Name Last Name Company CITY OF CHILOQUIN Address PO BOX 196 City CHILOQUIN State OR Zip 97624

(2) TYPE OF WORK [X] New Well [] Deepening [] Conversion [] Alteration (complete 2a & 10) [] Abandonment (complete 5a)

(2a) PRE-ALTERATION Dia + From To Gauge Stl Plstc Wld Thrd Casing: Seal:

(3) DRILL METHOD [] Rotary Air [X] Rotary Mud [] Cable [] Auger [] Cable Mud [X] Reverse Rotary [] Other

(4) PROPOSED USE [] Domestic [] Irrigation [X] Community [] Industrial/ Commercial [] Livestock [] Dewatering [] Thermal [] Injection [] Other

(5) BORE HOLE CONSTRUCTION Special Standard [] (Attach copy) Depth of Completed Well 1200.00 ft.

Table with columns: Dia, From, To, Material, From, To, Amt, sacks/lbs. Rows for Cement and Calculated values.

Seal placement method: [X] A [] B [X] C [] D [] E [] Other: Backfill placed from ft. to ft. Material Filter pack from ft. to ft. Material Size Explosives used: Type Amount Seal Placement Begin Date 9/11/2025 Begin Time 10:00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE Proposed Amount Actual Amount

(6) CASING/LINER Table with columns: C/L, Dia, +, From, To, Gauge, Mat. Type, Wld, Thrd, Shoe, Location. Row 1: C, 16, X, 3, 654, 0.375, ST, X, OUT., 654

Temp casing [X] Yes Dia 20 From + [X] 1 To 10

(7) PERFORATIONS/SCREENS Perf/ Casing/ Screen Screen Liner Dia From To Scrn/slot width Slot length # of slots Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Table with columns: Type of Test, Yield (gal/min), Drawdown, Drill Stem/ Pump Depth, Duration (hr). Row 1: Pump, 1200, 2, 500, 18

Temperature 52 °F Lab analysis [] Yes By Water quality concerns? [] Yes (describe below) TDS amount 60 ppm From To Description Amount Units

(9) LOCATION OF WELL (legal description) County KLAMATH Twp 34.00 S N/S Range 7.00 E E/W WM Sec 28 NE 1/4 of the SW 1/4 Tax Lot 100 Tax Map Number Lot Lat Long NEAREST 405 HWY 422 CHILOQUIN OR 97624

(10) STATIC WATER LEVEL Date SWL(psi) + SWL(ft) Existing Well / Pre-Alteration Completed Well 12/24/2025 130 Flowing Artesian? Dry Hole?

WATER BEARING ZONES Depth water was first found SWL Date From To Est Flow SWL(psi) + SWL(ft) 12/24/2025 658 1200 1200 130

(11) WELL LOG Ground Elevation 4310.53 FT Material From To Sand, red brown, medium, silty 0 3 Sandstone, grey, medium hard, fractured 3 4 Siltstone, tan, hard 4 10 Sandstone, grey, medium hard, fine to medium 10 14 Claystone, tan, medium, some clay, firm lenses 14 24 Clay, tan, fine to medium, sand, grey 24 27 Claystone, tan, medium, some sand, grey 27 47 Silt, brown, medium, medium firm 47 77 Siltstone, brown, medium hard 77 97 Silt, green grey, medium firm 97 100 Siltstone brown, medium hard 100 117 Silt, green gray, medium firm, w/sand & clay 117 137 Silt, grey, medium 137 150 Silt, purple, medium hard, some stone, light grey 150 160 Silt, green and purple, medium hard 160 180 Silt, green, with dark grey 180 197 Silt, dark grey, hard 197 225 Silt, green, medium soft, with dark grey 225 245 Silt, dark grey, medium hard, some soft 245 255 Construction Begin Date 7/14/2025 Begin Time 16:00 End Date 12/24/2025

(unbonded) Water Well Constructor Certification I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. License Number 1927 Date 12/31/2025 Signed RYAN SMITH (E-filed)

(bonded) Water Well Constructor Certification I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. License Number 1988 Date 2/1/2026 Signed ERIC SCHNEIDER (E-filed) Drilling Company: Schneider Water Services

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

KLAM 62344

2/1/2026

Map of Hole

**STATE OF OREGON
WELL LOCATION MAP**

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department
725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL
Latitude: 42.59439149 Datum: WGS84
Longitude: -121.88687430
Township/Range/Section/Quarter-Quarter Section:
WM34.00S7.00E28NESW
Address of Well:
NEAREST 405 HWY 422 CHILOQUIN OR 97624

Well Label: 154512
Printed: December 31, 2025

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.
Provided by well constructor

