

STATE OF OREGON
WATER SUPPLY WELL REPORT

KLAM 62439

WELL I.D. LABEL# L

Page 1 of 3

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/29/2026

START CARD #

ORIGINAL LOG #

160207

1082830

(1) LAND OWNER

Owner Well I.D.

First Name LANCE & KEM Last Name WATSON

Company

Address 4717 HASKINS RD

City BONANZA State OR Zip 97623

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal:

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 158.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	40.5	Bentonite Chips	0	40.5	26	S
6	40.5	166.5			Calculated	18.48	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED DRY&HYDRAT

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 7/20/2026 Begin Time 17 09

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe Location
C	6	☒	2.5	40.5	0.250	ST	☒		OUT. 40.5
L	4		12	158	Sch40	PL		☒	

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method Skillsaw Cut

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
		4	118	158	.125	6	80	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	30		140	1

Temperature 59 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 198 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County KLAMATH Twp 38.00 S N/S Range 11.00 E E/W WM

Sec 18 SW 1/4 of the SW 1/4 Tax Lot 1300

Tax Map Number Lot

Lat ° ' " or 42.27083759 DMS or DD

Long ° ' " or -121.46262978 DMS or DD

☐ Street address of well ☒ Nearest address

NORTH OF 4920 HASKINS RD

PARCEL #455634

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/20/2026			65
Flowing Artesian?	☐			
Dry Hole?	☐			

WATER BEARING ZONES

Depth water was first found 129.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/20/2026	129	166.5	40			65

(11) WELL LOG

Ground Elevation 4184.67 FT

Material	From	To
Rocky Top Soil	0	2
Black Sandrock	2	7
Brown Claystone	7	11
Gray Basalt	11	27
Gray Basalt & Seams of Brown Clay	27	32
Gray Basalt	32	129
Broken Gray Basalt WB	129	166.5

Construction

Begin Date 7/20/2026 Begin Time 11 02 End Date 7/20/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1983 Date 7/24/2026

Signed KYLE HUGHES (E-filed)

Drilling Company: Norm Sevey Well Drilling, Inc 541-882-3504

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

KLAM 62439

7/29/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 42.27083759 Datum: WGS84

Longitude: -121.46262978

Township/Range/Section/Quarter-Quarter Section:

WM38.00S11.00E18SWSW

Address of Well:

NORTH OF 4920 HASKINS RD

PARCEL #455634

Well Label: 160207

Printed: July 24, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

