

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

LAKE 1035 RECEIVED

275-17E-22dx

WATER WELL REPORT

JAN 21 1976

STATE OF OREGON

(Please type or print) WATER RESOURCES DEPT.

State Well No.

(Do not write above this line) SALEM, OREGON Permit No.

(1) OWNER:

Name Tim Puckett - Golden Rule Farms
Address Christmas Valley, Oregon

(2) TYPE OF WORK (check):

New Well ☐ Deepening ☒ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

4" Diam. from 0 ft. to 70 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Air test
Was a pump test made? ☒ Yes ☐ No If yes, by whom? C. Blaylock
Yield: 1500 gal./min. with 40 ft. drawdown after 2 hrs.
" " " "
" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 57° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Portland cement
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 17 in.
Diameter of well bore below seal 15" to 18" - 1" to 275'
Number of sacks of cement used in well seal 8 sacks
Number of sacks of bentonite used in well seal sacks
Brand name of bentonite
Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☐ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Dealer's well number #5
SE 1/4 S 1/2 Section 22 T. 27-5 R. 17-E W.M.
Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 39' ft.
Static level 22' ft. below land surface. Date 1-6-76
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 15" to 18" to 275'

Depth drilled 275 ft. Depth of completed well 275 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil, Brown	0	4	
Clay, Green	4	175	216"
Sand, Bk, coarse, water bearing	175	185	
Rock, Bk, very hard	185	240	
Sand, Bk, coarse, some clay	240	244	22'
Rock, Bk, very hard	244	253	
Sand, coarse, gravel, fine, W.B.	253	256	
Rock, Bk, very hard	256	275	

JAN 21 1976

WATER RESOURCES DEPT.

SALEM, OREGON

Work started 1-3-76 19 Completed 1-6-76 19

Date well drilling machine moved off of well 1-6-76 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Alvin Behnke Date 1-6-76 19
(Drilling Machine Operator)

Drilling Machine Operator's License No. 960

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Orville Beckner
(Person, firm or corporation) (Type or print)

Address 2586 S.W. 20th Ave. Redmond

[Signed] Orville Beckner
(Water Well Contractor)

Contractor's License No. 608 Date 1-6-76 19