

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON JUN 12 1975

(Please type or print)

STATE ENGINEER
SALEM, OREGON

State Well No.

State Permit No.

Hand # 8787777

(1) OWNER:

Name Jack L Gillette
Address Box 192
Christmas Valley, Or 97638

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐
Cable ☒

Driven ☐
Jettied ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☐

1 1/4" Diam. from 0 ft. to 120 ft. Gage 1 1/4"
" Diam. from " ft. to " ft. Gage "
" Diam. from " ft. to " ft. Gage "

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No. If yes, by whom? OWNER
Yield: 2400 gal./min. with 17 ft. drawdown after 4 hrs.
" " " " " "
" " " " " "

Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.

Temperature of water 54°F Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 120 ft.
Diameter of well bore to bottom of seal 18 in.
Diameter of well bore below seal 14 in.
Number of sacks of cement used in well seal 20 sacks
Number of sacks of bentonite used in well seal NONE sacks
Brand name of bentonite _____

Number of pounds of bentonite per 100 gallons
of water _____ lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs 1 x 1/2 Size; location 120 ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Lake Driller's well number _____
SE 1/4 SW 1/4 Section 7 T. 27 R. 18 W.M.

Bearing and distance from section or subdivision corner

1930 Ft East 1210 Ft North
of SW corner of section 7

(11) WATER LEVEL: Completed well.

Depth at which water was first found 58 ft.

Static level 19 ft. below land surface. Date _____

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 14 1/4 to 4 1/2

Depth drilled _____ ft. Depth of completed well 620 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Sandy loam	0	3	
Soft gray clay.	3	37	
Hard gray sandstone.	37	58	
Fine gray sand.	58	60	19'
gray clay (soft)	60	88	
Hard brown clay.	88	137	
Fine brown gravels.	137	138	
light gray clays (soft)	138	226	
coarse humic sand.	226	228	
Soft gray clay	228	288	
Soft brown clay.	288	315	
Soft gray clay.	315	355	
Fine gray sand.	355	356	20'
Soft gray clay.	356	417	
Fine humic sand.	417	418	
Soft gray clay.	418	446	
Fine black cinders.	446	448	
light brown soft clay.	448	510	
Fine black cinders.	510	511	

Work started 12/10 1975 Completed 5/15 1975

Date well drilling machine moved off of well 5/20 1975

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Jack L Gillette Date 6/2, 1975
(Drilling Machine Operator)

Drilling Machine Operator's License No. 007

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name _____
(Person, firm or corporation) (Type or print)

Address _____

[Signed] _____
(Water Well Contractor)

Contractor's License No. _____ Date _____, 19____

