

WATER WELL REPORT
STATE OF OREGON

RECEIVED

JUL 21 1981

State Well No.

25S/14E-15C4

WATER RESOURCES DEPT
SALEM, OREGON

State Permit No.

T-5575 & 5576

(1) OWNER:

Name Bob Reed
Address Long Delivery
City Fl. Rock State Cal

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
☐ Bored ☐ Thermal: ☒ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☐ Plastic ☐
Threaded ☐ Welded ☒

14" Diam. from 0 ft. to 5.5 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Is a pump test made? ☐ Yes ☒ No If yes, by whom?

Test: gal./min. with ft. drawdown after hrs.

Air test 1200 gal./min. with drill stem at 367 ft. 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 5.5 ft.
Diameter of well bore to bottom of seal 1.7 in.
Diameter of well bore below seal 13 1/2 in.
Number of sacks of cement used in well seal 49 sacks
How was cement grout placed? pressure grouted

Was pump installed? n.o. Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number 160
SE 1/4 SW 1/4 Section 15 T. 25S R. 14E W.M.
Tax Lot # Lot Blk Subdivision

Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found ft.

Static level 40 ft. below land surface. Date July 16-81

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 13 1/2

Depth drilled 367 ft. Depth of completed well 367 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Sandy brown	0	2	
Gray clay	2	5.5	
Gray basalt—hard	5.5	7.5	
Brown sandstone	7.5	24.2	
Green shale	24.2	25.5	
Green clay	25.5	30.5	
black sand w/b	30.5	31.0	40
Green clay	31.0	35.0	
black sand seams w/b	35.0	35.8	40
Green shale	35.8	36.7	

Work started July 1 19 81 Completed July 16 19 81
Date well drilling machine moved off of well July 16 19 81

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Tyler Adams Date July 17, 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1292

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Tyler Adams (Type or print)
(Person, firm or corporation)

Address 1000 N. Hill St. Lake Ore. 97638

[Signed] Tyler Adams (Water Well Contractor)

Contractor's License No. 690 Date July 17, 19 81

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP12658-690