

WATER WELL REPORT
STATE OF OREGON

State Well No. 255-14E-28 aa
State Permit No. G-9230

Lake 132

(1) OWNER:

Name Dave Pick
Address 4235 W Antler
City Redmond State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
Cable ☒ Bored ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

CASING INSTALLED: Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
14" Diam. from +11 ft. to 91 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal/min. with ft. drawdown after hrs.
" " " "
Pump test 1300 gal/min. with drill stem at 100 ft. 2 hrs.
Bailer test gal/min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 52 Depth artesian flow encountered none ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Portland Cement, Type I
Well sealed from land surface to 20' ft.
Diameter of well bore to bottom of seal 18 in.
Diameter of well bore below seal 14 in.
Number of sacks of cement used in well seal 40 sacks
How was cement grout placed? Pressure pumped

Was pump installed? no Type HP Depth ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of Water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number 84
NE 1/4 NE 1/4 Section 28 T. 25S R. 14E W.M.
Tax Lot # Lot Blk Subdivision

Address at well location: Fort Rock, Oregon
1310' from the South Line, and 1310 from the East

(11) WATER LEVEL: Completed well.

Depth at which water was first found 50 ft.
Static level 50 ft. below land surface. Date 12-20-80
Artesian pressure none lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 14

Depth drilled 280 ft. Depth of completed well 280 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil Brown	0	4	
Brown Clay	4	43	
Course Black Sand WB	43	87	50
Gray Broken Rock	87	114	
Fine Black Sandstone	114	128	
Blue Clay	128	141	
Medium Black Sand	141	157	
Brown Clay	157	178	
Gravel Congl	178	205	
Blue Clay	205	215	
Brown Congl	215	234	
Brown Clay	234	247	
Brown Congl	247	280	

RECEIVED

FEB 9 1981

WATER RESOURCES DEPT
SALEM, OREGON

Work started 12-8-80 19 Completed 1-5-81 19
Date well drilling machine moved off of well 1-5-81 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Bill Williams Date 1-12-81
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1231

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Bill Williams Well Drilling
(Person, firm or corporation) (Type or print)

Address P.O. Box 334, Redmond, Oregon 97756

[Signed] Bill Williams
(Water Well Contractor)

Contractor's License No. 782 Date Jan 12, 1981, 19

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.