

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print) STATE ENGINEER

(Do not write above this line) SALEM, OREGON

RECEIVED

JUN 4 1975

State Well No. 295/17E-26

State Permit No.

(1) OWNER:

Name Bud Palmer
Address 7823 East Clinton Ave.
Fresno California 93703

(2) TYPE OF WORK (check):

New Well ☐ Deepening ☐ Reconditioning ☒ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
10" Diam. from 0 ft. to 204 ft. Gage 3/8 in.
8" Diam. from 180 ft. to 370 ft. Gage 3/16 in.

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch
Size of perforations 1/4 in. by 2 1/2 in.
6 per Ft. perforations from 204 ft. to 370 ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
" " " " " "

Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow 350 g.p.m.

Temperature of water 55 Depth artesian flow encountered 346 ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 204 ft.
Diameter of well bore to bottom of seal 14 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 68 sacks
Number of sacks of bentonite used in well seal none sacks
Brand name of bentonite _____
Number of pounds of bentonite per 100 gallons
of water _____ lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs ☒ Size: location 204 ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County LAKE Driller's well number _____
NW 1/4 SE 1/4 Section 26 T. 29S R. 17E W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 64 ft.
Static level 46 ft. below land surface. Date 9-6-73
Artesian pressure 8 lbs. per square inch. Date 5-4-75

(12) WELL LOG:

Diameter of well below casing 8 in.

Depth drilled Reamed only ft. Depth of completed well 370 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Sandy Loam	0	4	
Soft Grey clay	4	45	
Fine Black sand	45	64	
Soft Grey clay	64	90	
Fine Black sanders	90	92	
Soft Blue clay	92	152	
Hard Brown clay	152	171	
Hard Grey claystone	171	212	
Hard Red clay	212	235	
Hard Brown clay	235	290	
Hard Red clay	290	346	
Coarse Red sanders	346	368	
Solid Grey Lava Rock	368	370	

Work started 6-18 1973 Completed 5-4 1975
Date well drilling machine moved off of well 5-4 1975

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Silas Blaylock Date 6-2, 1975
(Drilling Machine Operator)

Drilling Machine Operator's License No. 383

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Blaylock and Woods Drilling
(Person, firm or corporation) (Type or print)

Address Box 2 Silver Lake Ore.

[Signed] Silas Blaylock
(Water Well Contractor)

Contractor's License No. 425 Date 6-2, 1975