

WATER WELL REPORT
STATE OF OREGON

RECEIVED

AUG 4 1983

State Well No. 295/17E-360a

WATER RESOURCES DEPT.
SALEM, OREGON

State Permit No.

(1) OWNER:

Name Gilbert Kohfield
Address 2547E Mehlo Circle
City Fresno State CA. 93710

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐ Domestic ☐ Industrial ☐ Municipal ☐
Mud ☐ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
☒ Bored ☐ Thermal: ☒ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED: Steel ☐ Plastic ☐
Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 202 ft. Gauge 1/4 wall
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Is a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow 600 g.p.m.

Temperature of water 62 Depth artesian flow encountered 81 ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement

Well sealed from land surface to 200 ft.

Diameter of well bore to bottom of seal 13 in.

Diameter of well bore below seal 8 in.

Number of sacks of cement used in well seal 211 sacks

How was cement grout placed? pumped from

Bottom up

Was pump installed? No Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs 1/4x6 Size: location 200 ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake Driller's well number
NE 1/4 SE 1/4 Section 36 T. 29S R. 17E W.M.
Tax Lot # 2600 Lot Blk Subdivision

Address at well location: 8 miles East of Summer Lake Oregon

(11) WATER LEVEL: Completed well.

Depth at which water was first found 26 ft.

Static level 4 ft. below land surface. Date 7-3-81

Artesian pressure 5 lbs. per square inch. Date 7-5-83

(12) WELL LOG: Diameter of well below casing 8 1/2 inch

Depth drilled 495 ft. Depth of completed well 495 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top Soil	0	2	
Soft Blue Clay	2	22	
Fine Grey Sand	22	26	4
Soft Blue Clay	26	36	
Hard Blue Cube clay	36	40	
Hard Black pack Sand	40	55	
Soft Silt	55	81	
Hard Grey Clay	81	189	
Hard Claystone	189	415	
Decomposed Red Lava Rock	415	460	
Hard Coarse Red Cinders	460	495	

Water came out of Red Cinders at 460 ft. And increased with Depth

Work started 7-3 1981 Completed 7-5 1983

Date well drilling machine moved off of well 7-10 1983

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Silas Blaylock Date 8-1, 1983
(Drilling Machine Operator)

Drilling Machine Operator's License No. 783

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Silas Blaylock (Person, firm or corporation) (Type or print)

Address Box 1 Silver Lake Ore. 97638

[Signed] Silas Blaylock (Water Well Contractor)

Contractor's License No. 425 Date 8-1, 1983

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690