

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON

Please type or print

(Do not write above this line)

State Well No.

State Permit No.

STATE ENGINEER

SALEM, OREGON

(1) OWNER:

Name Jim Foster
Address Summer Lake, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

6" Diam. from 0 ft. to 140 ft. Gage .250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 0 ft. below land surface Date 6/20/69
Artesian pressure 10 lbs. per square inch Date 6/20/69

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? L. Reed
Yield: 70 gal./min. with 15 ft. drawdown after 2 hrs.
" " " "

Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow 40 g.p.m. Date 6/18/69
Temperature of water 64 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement
Depth of seal 55 ft. ft.
Diameter of well bore to bottom of seal 8 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Did any strata contain unusable water? ☒ Yes ☐ No
Type of water? palatable depth of strata (13--15)
Method of sealing strata off cement (36--36½)
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Lake Driller's well number
SE ¼ NE ¼ Section 24 T. 30 R. 17E W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 210 ft. Depth of completed well 210 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Sand, fine	0	1	
Clay, light brn.	1	4	
Sand, grey	4	4½	
Clay, light brn.	4½	13	
Pumice, white	13	15	0
Clay, blue	15	16	
Clay, light brn	16	36	
Pumice, white	36	36½	0
Clay, blue	36½	50	
Rock, cemented	50	51	
Clay, multi color, blue	51	184	
grey, light brn.			
Lava, brn, dense	184	189	0
Cinders, red course	189	210	0

Well was cemented from 0 to 55 ft. with cement slab at top

Valve and pressure guage installed

Work started 6/9/ 1969 Completed 6/18 1969

Date well drilling machine moved off of well 6/20/ 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Larry Reed Date 6/27, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 130

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Reed's Well Drilling
(Person, firm or corporation) (Type or print)

Address 1142 Galveston Bend, Oregon

[Signed] Larry Reed
(Water Well Contractor)

Contractor's License No. 443 Date 6/27/ 1969