

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

State Well No. 3571

State Permit No. 1571

(1) OWNER:

Name VERLE EMERY
Address SUMMER LAKE OREGON 47646

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

2" Diam. from 0 ft. to 240 ft. Gage 0-250
8" Diam. from 220 ft. to 230 ft. Gage 0-250
" Diam. from " ft. to " ft. Gage "

(6) PERFORATIONS:

Perforated? ☐ Yes ☐ No.

Size of perforator used

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☐ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? OWNER

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " "

Bailer test 1200 gal./min. with 6 ft. drawdown after 24 hrs.

Artesian flow 0 g.p.m.

Temperature of water 67 Depth artesian flow encountered _____ ft.

CONSTRUCTION:

Well seal—Material used CEMENT GROUT
Well sealed from land surface to 22 FT ft.
Diameter of well bore to bottom of seal 16 in.
Diameter of well bore below seal 12 in.
Number of sacks of cement used in well seal 10 sacks
How was cement grout placed? PRESSURE PUMP

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.

Did any strata contain unusable water? ☒ Yes ☐ No

Type of water? SURFACE depth of strata 10 FT

Method of sealing strata off CEMENT GROUT

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County LAKE Driller's well number 1
NW 1/4 NW 1/4 Section 35 T. 31S R. 16E W.M.

Bearing and distance from section or subdivision corner

960' S 890' E NW CORNER OF SEC 35
1/4 1/4 1/4

(11) WATER LEVEL: Completed well.

Depth at which water was first found 250 ft.

Static level 20 ft. below land surface. Date 4/10/80

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 468 ft. Depth of completed well 468 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
SANDY LOAM	0	12	
BROWN CLAY	12	110	
BLUE CLAY	110	235	
HARD ROCK	235	240	
" "	240	250	20
CINDERS	250	285	20
BOULDERS	285	300	20
" "	300	365	20
CINDERS	365	425	20
COARSE GRAVEL	425	468	20

RECEIVED
JUL 14 1995

WATER RESOURCES DEPT
SALEM, OREGON

Work started 15/9/79 19 Completed 1/1/80 19

Date well drilling machine moved off of well 1/10/80 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] L. C. Kristensen Date 2/12/80, 19____
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1238

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name _____
(Person, firm or corporation) (Type or print)

Address _____

[Signed] _____
(Water Well Contractor)

Contractor's License No. _____ Date _____, 19____