

NOTICE TO WATER WELL CONTRACTOR:
The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

(Do not write above this line)

RECEIVED
MAY 3 1973

State Well No.

STATE ENGINEER

SALEM, OREGON

State Permit No.

(1) OWNER:

Name John V. Withers

Address Rt. 1, Box 200, Paisley, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐
Cable ☒
Dug ☐

Driven ☐
Jetted ☐
Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
14" Diam. from 0 ft. to 301 ft. Gage .250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch-Cut

Size of perforations 3/32 in. by 6 in.
1,512 perforations from 47 ft. to 291 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller

Rate: 1,000 gal./min. with 100 ft. drawdown after 35 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water 64 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 20 in.

Diameter of well bore below seal 14 in.

Number of sacks of cement used in well seal 10 sacks

Number of sacks of bentonite used in well seal 0 sacks

Brand name of bentonite

Number of pounds of bentonite per 100 gallons

of water lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs 0 Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lake

Driller's well number

SE 1/4 NE 1/4 Section 10 T. 33 R. 18 E.W.M.

Bearing and distance from section or subdivision corner

Four Miles north of Paisley, Oregon

(11) WATER LEVEL: Completed well.

Depth at which water was first found 40 ft.

Static level 40 ft. below land surface. Date 5-1-73

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 14"

Depth drilled 306 ft. Depth of completed well 306 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
SOIL Zone (gravelly)	0	2	
Gravel & Clay (brown)	2	60	40
Gravel (med.-coarse, with Cemented areas)	60	102	
Clay & Gravel (blue)	102	123	
Gravel (loose) & Clay brown	123	150	
Sandy Clay (blue)	150	157	
Gravel (med., blue)	157	205	
Clay & Gravel (blue)	205	280	
Clay & Gravel (brown)	280	293	
Clay (brown)	293	306	

Work started 4-4-1973 Completed 5-1-1973

Date well drilling machine moved off of well 5-2-1973

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Sary Stooksberry Date 5-1-1973
(Drilling Machine Operator)

Drilling Machine Operator's License No. 801

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Jack Stooksberry, Jr.
(Person, firm or corporation) (Type or print)

Address Rt. 2, Box 47, Lakeview, Oregon

[Signed] Jack Stooksberry Jr.
(Water Well Contractor)

Contractor's License No. 211 Date 5-1-1973